	OWNER:		
		Sheet Number	
	B2 CONTRACTING 180 WALTER WAY #110	C000	COVER
	FAYETTEVILLE, GA 30214	C001 C100	GENERAL NOTES
	CONTACT: BRANDON HARP EMAIL: BHARP@B2CONTRACTING.COM	C200	SITE PLAN
	PHONE: (770) 789-2123	C300	GRADING AND DRAINAGE
	ENGINEER:	C351	STORM PIPE CHARTS
	HIGHLAND LAND PLANNING	C400	UTILITY PLAN
	201 PROSPECT PARK, SUITE A PEACHTREE CITY, GA 30269	C500	EROSION CONTROL COVER
	CONTACT: REID K ALMAND, P.E.	C501	COMPREHENSIVE MONITOR
	EMAIL: REID.ALMAND@HIGHLANDLP.US PHONE: (770) 631-0499	C502 C503	N.P.D.E.S. CHECKLIST
	SURVEYOR:	C510	INITIAL PHASE EROSION ANI
		C520	INTERMEDIATE PHASE EROS
	W.S. BODKIN SURVEYING, LLC 315 CAASTLEWOOD RD	C530	FINAL PHASE EROSION AND
	TYRONE, GA 30290 CONTACT: SCOTT BODKIN, R.L.S.	C600	EROSION DETAILS
	PHONE: (770) 312-5500	C601	EROSION DETAILS
	ZONING: IHV, HEAVY INDUSTRIAL	C602 C700	EROSION DETAILS
		C700	CONSTRUCTION DETAILS
	TOTAL SITE AREA = 8.31 +/- AC. DISTURBED AREA = 3.90 AC.	C702	CONSTRUCTION DETAILS
	IMPERVIOUS SURFACE CALCULATIONS: IMPERVIOUS 0.76 AC., GRAVEL 1.38 AC.,	C703	CONSTRUCTION DETAILS
	TOTAL IMPERVIOUS FOR WQV CALCULATIONS (GRAVEL @ 85%) 1.93 AC.	C704	CONSTRUCTION DETAILS
	LOT DIMENSION REQUIREMENTS PER CITY OF NEWNAN ZONING ORDINACE:	C705	CONSTRUCTION DETAILS
	MINIMUM LOT SIZE - 2 ACRES (87,120 SF) FRONT SETBACK: MAJOR STREET = 40 / 100 FT, MINOR STREET = 40 / 65 FT	C706	CONSTRUCTION DETAILS
	SIDE SETBACK: 30 FT	L100	L100 LANDSCAPE PLAN
	STREET SIDE SETBACK: MAJOR STREET = 40 / 100 FT, MINOR STREET = 40 / 65 FT REAR SETBACK: 40 FT		
	MINIMUM BLDG LINE WIDTH:200 FT MINIMUM LOT FRONTAGE: 200 FT		
	MINIMUM LOT DEPTH: 200 FT		
	PRINCIPLE BUILDING HEIGHT: 35 FT ACCESSORY BUILDING HEIGHT: 35 FT		
	MAXIMUM BUILDING COVERAGE 60% (LOT) BASE/MAXIMUM FLOOR AREA RATIO: 0.30 / 0.50		
	DISTANCE BETWEEN BUILDINGS: 25 FT		
	LANDSCAPE STRIP 10 FT PERIMETER		
	VEHICLE STORAGE SUMMARY: TOTAL REQUIRED: OFFICE: 1/ 250 SQ. FT. OF GFA = 6,400 SQ. FT. GFA = 26 SPACES SHOP/WAREHOUSE: 0.25/1000 SQ. FT. = 4,000 SQ FT = 1 SPACES TOTAL = 27 SPACES		
	TOTAL = 27 SPACES TOTAL PROVIDED = 27 SPACES (1 HANDICAP SPACES)		
	24 HOUR CONTACT: BRANDON HARP, (770) 789-2123		
	STATE WATERS ARE PRESENT ON THIS PROJECT SITE AS INDICATED, HOWEVER ARE NOT AFFECTED BY THIS DEVELOPMENT.		
	WETLANDS WERE NOT IDENTIFIED WITHIN THE PROPERTY BOUNDARY.		
-	PROJECT SITE IS NOT LOCATED WITHIN A GROUND WATER RECHARGE AREA		
	A PORTION OF THIS PROPERTY IS LOCATED WITHIN A FLOOD HAZARD AREA ACCORDING TO F.E.M.A. FLOOD INSURANCE RATE MAP FOR COWETA COUNTY COMMUNITY PANEL #13077C0143D DATED FEB. 6, 2013.		
	WATER AND SEWER SERVICE TO BE PROVIDED BY NEWNAN UTILITIES.		
	ALL WORK SHALL CONFORM TO CITY OF NEWNAN STANDARDS AND SPECIFICATIONS. IT IS THE CONTRACTORS RESPONSIBILITY TO NOTIFY THE PROPER OFFICIALS FOR ANY REQUIRED INSPECTIONS.		
	NO GDOT PERMITS APPLICABLE TO THIS DEVELOPMENT.		Γ
	NO ARMY CORPS PERMITS APPLICABLE TO THIS DEVELOPMENT.		
R	AINAGE EASEMENT NOTE:	\sim	کې <
	THE OWNER OF RECORD, ON BEHALF OF HIMSELF (ITSELF) AND ALL SUCCESSORS IN INTEREST SPECIFICALLY RELEASES THE CITY OF NEWNAN FROM ANY AND ALL LIABILITY AND RESPONSIBILITY FOR FLOODING OR EROSION FROM STORM DRAINS OR FROM FLOODING FROM HIGH WATER OF NATURAL CREEKS, RIVERS OR DRAINAGE FEATURES SHOWN HEREIN. A DRAINAGE EASEMENT IS HEREBY ESTABLISHED FOR THE THE SOLE PURPOSE OF PROVIDING FOR THE EMERGENCY PROTECTION OF THE FREE FLOW OF SURFACE WATERS ALONG ALL WATERCOURSES AS ESTABLISHED BY THE REGULATIONS OF THE CITY OF NEWNAN. THE PUBLIC WORKS DIRECTOR MAY CONDUCT EMERGENCY MAINTENANCE OPERATIONS WITHIN THIS EASEMENT WHERE EMERGENCY CONDITIONS EXIST. EMERGENCY MAINTENANCE SHALL BE THE REMOVAL OF TREES AND OTHER DEBRIS, EXCAVATION, FILLING AND THE LIKE, NECESSARY TO REMEDY A CONDITION, WHICH IN THE JUDGMENT OF THE PUBLIC WORKS DIRECTOR, IS		NEWNAN
YI	POTENTIALLY INJURIOUS TO LIFE, PROPERTY OF THE PUBLIC ROADS OR UTILITY SYSTEM. SUCH EMERGENCY MAINTENANCE, CONDUCTED FOR THE COMMON GOOD, SHALL NOT BE CONSTRUED AS CONSTITUTING A CONTINUING MAINTENANCE OBLIGATION ON THE PART OF THE CITY OF NEWNAN NOR AN ABROGATION OF THE CITY'S RIGHTS TO SEEK REIMBURSEMENT FOR EXPENSES FROM THE OWNERS OF THE PROPERTY/IES OF THE LANDS THAT GENERATED THE CONDITIONS.		لی COWE COUN
	THE EXISTING WET EXTENDED DETENTION POND ON-SITE WAS DESIGNED AND INSTALLED AS	L	
	THE EXISTING WET EXTENDED DETENTION POND ON-SITE WAS DESIGNED AND INSTALLED AS PART OF THE HYDROLOGICAL REPORT FOR INCONTROL, INC. BY SEABOLT & CO., INC. DATED 6/9/2008. AS PART OF THIS DEVELOPMENT, AN ASBUILT SURVEY WAS PERFORMED ON THE OUTLET CONTROL STRUCTURE AND THE VOLUME OF THE POND. THE DESIGN OF THE WATER QUALITY COMPONENT OF THE POND ACCOUNTED FOR 2.05 ACRES OF IMPERVIOUS AREA DRAINING TO IT. THIS PROPOSED DEVELOPMENT INCLUDES 0.76 ACRES OF IMPERVIOUS SURFACES AS WELL AS 1.38 ACRES OF GRAVEL SURFACES. IN ORDER TO ACCOUNT FOR THE	PREPA	ARED FOR:

OF USING A RUNOFF REDUCTION PRACTICE.

List Table
E
VER
TORING PLAN
AND SEDIMENTATION CONTROL PLAN
ROSION AND SEDIMENTATION CONTROL PLAN
AND SEDIMENTATION CONTROL PLAN
S
S
S
S
S


SITE DEVELOPMENT PLANS FOR B2 CONTRACTING WORLD HEADQUARTERS

LAND LOT 73 & 74 OF THE 5th DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA SITE ADDRESS: 141 HILLWOOD CIRCLE

GPS LOCATION OF THE CONSTRUCTION EXIT LAT: 33.3974668° LONG: -084.7820601°

SITE LOCATION MAP







CITY OF NEWNAN SPECIAL NOTES:

DRAINAGE EASEMENT NOTE: The owner of record, on behalf of himself (itself) and all successors in interest specifically releases the city of newnan from any and all liability and responsibility for flooding or erosion from storm drains or from flooding om high water of natural creeks, rivers or drainage features shown herein. a drainage easement is hereby established for the sole purpose of providing for the emergency protection of the free flow of surface waters along all watercourses as established by the regulations of the city of newnan, the public works direct or may conduct emergency maintenance operations within this easement where emergency conditions exist. emergency maintenance shall be the removal of trees and other debris, excavation, filling and the like, necessary to remedy a condition, which in the judgment of the public works director, is otentially injurious to life, property or the public roads or utility system. such emergency maintenance, conducted for the common good, shall not be construed as constituting a continuing maintenance obligation on the part of the city of newnan nor an abrogation of the city's rights to seek reimbursement for expenses from the owner/s of the property/ies of the lands that generated the conditions.

The approval of these plans and the issuance of this land disturbance permit does not in any way suggest that all other equirements for the legal or appropriate operations for this activity, which may require additional permitting have been met. ne onus is on the Owner/Developer/Builder to discover what additional permitting or approvals may be necessary to operate rom this point in an appropriate and legal manner. Plan approval or permit issuance does not absolve the applicant from mplying with all applicable laws, standards, or other permits which may be required for this project.

COMPACTION TEST: Compaction test will be required in existing or proposed streets, sidewalks, drives, and other existing or proposed paved areas at varying depths and at intervals as determined by the City Engineer. Unless otherwise noted all backfil in the right of way shall be compacted to 95% standard proctor per ASTM D 698. Contact Ray Norton for proof rolls at 404-606-9140 and send all compaction test results to shenriquez@cityofnewnan.org and rnorton@cityofnewnan.org

- Subgrade (at least one test per 1,500 linear feet alternating lanes and one in each cul-de-sac), if less than 1,500 linear feet then one per day/per section constructed, must also pass proof roll. Base (at least one per 1,500 linear feet alternating lanes and one in each cul-de-sac), if less than 1,500 linear feet then one
- per day/per section constructed, must also pass a proof roll. Curb and Gutter (rock beneath C&G), must pass a proof roll before curb and gutter is poured. Pipes – One test per lift on alternating sides of pipe for each 300 linear feet of pipe or portion thereof. Test pattern is to
- begin after first compactive layer above structures bedding and continue to 1 foot above top of pipe. Manholes -In the top 5 feet, minimum of one test every other lift around the perimeter of structure and continue to top of structure.

SITE PREP & TREE PROTECTION INSPECTION: Prior to clearing, or clearing and grubbing of the property or any portion icluded under the development permit, the developer must call for an INITIAL inspection of erosion and sedimentation control neasures and protective devices to include tree protection fence. Inspection of these measures will then be conducted on a ntinuing basis

PERMENANT PONDS: Upon completion of permanent detention ponds that are not otherwise used for sediment storage. If ponds are concrete the developer must call for footing inspections and wall inspections prior to pouring concrete.

STORM PIPES: Upon installation of storm drainage pipe or other storm water facilities underneath public roads prior to ackfilling and during compaction. Inspections will include storm pipe and structure connections, bedding, grout outside and nside, poured inverts, proper compaction of backfill, detention pond – contact Rob Hill for these inspections his direct line is 78-673-5477 or email at rhill@cityofnewnan.org.

CCTV INSPECTION OF STORM SEWER INFRASTRUTURE: Storm Sewer Infrastructure shall have a CCTV inspection prior acceptance by the City. All CCTV inspections will be conducted in accordance with the National Association of Sewer Service Companies, Inc. (NASSCO) Pipeline Assessment Certification Program (PACP). Certified assessment reports, repair ecommendations and DVDs will be submitted to Public Works by the owner's engineer. Public Works will review the reports and recommendations and approve or revise recommended remedial action on piping, structures, and backfill and street ections. Storm drainage systems: CCTV of storm drainage systems will be conducted after subbase stone has been compacted and setup, just prior to placement of first lift of pavement surface, but not less than 30 days after installation and ackfill to allow for consolidation and settlement of backfill material.

CURB AND GUTTER: Street curbing and gutter (if provided). Inspection shall be requested before the orms or string lines have been set to verify GAB depth and compaction beneath Curb and Gutter and after forms or string lines nave been set to verify alignment and layout. Street width and vertical and horizontal alignment will also be spot-checked.

SUB-GRADE STREETS: Sub-grade of streets shall be inspected after compaction and receipt of test reports by the City ngineer or his/her designee. The sub-grade must be roll tested with an eighteen (18) ton load on a tandem dump truck and all pass to the satisfaction of the City Engineer or his/her designee.

BASE STREETS: Street base shall be inspected after receipt of test reports by the City Engineer or his/her designee; the base nust be string-lined for depth and crown. The street base must be roll-tested with an 18-ton load on a tandem dump truck and shall pass to the satisfaction of the City Engineer or his/her designee.

PAVING STREETS: An inspector may be on site during the paving process to check consistency, depth, and workmanship, as applicable. For asphalt paving, the temperature of the material will be monitored and the street will be cored after completion to check thickness and density. Satisfactory test results of the cores shall be delivered to the City Engineer or his/her designee or to approval of a final subdivision plat or certificate of occupancy.

SIDEWALKS: Pre-pour forms inspection will include: compacted subgrade, optimum moisture, free of organics and debris, cross slope not to exceed 2%, 5-6 feet wide (reference plans) with 2-4 foot grass strip unless noted otherwise, expansion joints at all cold joints, around structures and every 60 feet, contraction joints spaced 5 to 6 feet apart depending on sidewalk width nd pattern (picture frame/streetscape), ramps per GDOT with truncated domes set in concrete yellow is the preferred color.

a accordance with the City of Newnan Sidewalk Regulations, prior to commencement of work, the Engineering Department, vill conduct an assessment on the condition of existing sidewalks. The developer is to be responsible to place, replace, repair, and correct any code violations, and bring existing sidewalks abutting their project site into compliance. This includes the oordination for relocation of existing utilities when necessary. This work shall be performed in coordination with city of Newnan gineering Department.

ILT FENCE: Newnan only allows the use of Type "S" silt fence or approved Type "S" Alternatives. Silt fence has a useful life 6 (six) months generally.

STRIPING AND SIGNAGE: Submit artwork for street name signs to Michael Klahr at mklahr@cityofnewnan.org for approval fore signs are ordered. Road acceptance will not occur until all regulatory signs, street name signs, and thermoplastic striping are in place.

TREET CUT NOTE: For utility crossings under existing roads, use directional bore or jack and bore unless approved by the tity Engineer. If pavement cuts are proposed provide a detail for approval by the City Engineer.

NOI: A copy of the N.O.I and proof of fees paid to the GA EPD shall be delivered to the Engineering Department, Attn: City ngineer, prior to approval of these development plans or a land disturbance permit being issued.

AS-BUILTS: "As-Built" drawings shall be submitted to the City Engineer prior to street acceptance. These shall include all ormation contained on the approved construction drawings in the "As-Built" state. All "as-built" drawings shall be submitted in both hard copy and digital format and be on the state plane coordinate system, USA, GA, NAD 83, West. The digital copy shall be in AutoCAD file format and pdf format.

TREET SIGNS (PUBLIC): Street name signs shall be: 9 inch Blades, Double Sided, white letters on green background, with City seal (furnished). Lettering in accordance with MUTCD Section 2D.43, and D3-1 in Figure 2D-10. No border, high intensity Prismatic, Not to exceed 48 inches in length, scale letters as appropriate to meet this length requirement. Abbreviations in cordance with MUTCD Table 1A-1. Standard post system, GDOT Type 7, installed in accordance with GDOT installation standard. Install over STOP sign, lower blade perpendicular to STOP sign, use 12 inch brackets. Submit artwork for each sign o City Engineer for approval prior to making signs.

RETAINING WALLS: Retaining walls that are 4 feet and over must be designed by qualified engineer. These will require parate submittals with factor of safety calculations and all dimensions, details, plan and profile drawings, picture, material ype with guardrail at top where necessary, etc. A separate permit will be required for each wall that is 4 feet or higher. Third arty inspections will be required to include but not limited to the footing, rebar, grid, soil, concrete, drains, and final inspection. n engineer's certification that the wall was installed according to the design is also required and must be submitted to the Engineering Department prior to final approval of the project or certificate of occupancy. If the wall is in an overlay district it nust be faced or finished to be more decorative and in compliance with the overlay district standards which are approved by he Planning Department.



							RKA	Date Apr.
							5/6/24	Date
							1. ISSUED FOR REVIEW	Rev. Description
ž							1.	Rev.
Check b	RKA							
Drawn by:	EAM RKA							
Date:	5/6/24							
				COVFR				
	SITE DEVELOPMENT PLANS			BZ CUNIKACIING	WOBI DITE A DOLLA BTEDS	WUKLD READYUANIEKS		LAND LOTS 73 AND 74 OF THE 5TH DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA
C IN E E RANDO								

DRAWING NO. C000

GE	NERAL NOTES:
1.	OWNER:
	B2 CONTRACTING 180 WALTER WAY #110 FAYETTEVILLE, GA 30214 CONTACT: BRANDON HARP EMAIL: BHARP@B2CONTRACTING.COM PHONE: (770) 789-2123
2.	ENGINEER:
	HIGHLAND LAND PLANNING 201 PROSPECT PARK, SUITE A PEACHTREE CITY, GA 30269 CONTACT: REID K ALMAND, P.E. EMAIL: REID.ALMAND@HIGHLANDLP.US PHONE: (770) 631-0499
3.	SURVEYOR:
	W.S. BODKIN SURVEYING, LLC 315 CAASTLEWOOD RD TYRONE, GA 30290 CONTACT: SCOTT BODKIN, R.L.S. PHONE: (770) 312-5500
4.	ZONING: IHV, HEAVY INDUSTRIAL
5.	TOTAL SITE AREA = 8.31 +/- ACRES TOTAL DISTURBED AREA: 3.90 ACRES IMPERVIOUS 0.76 AC., GRAVEL 1.38 AC., TOTAL IMPERVIOUS FOR WQV CALCULATIONS (GRAVEL @ 85%) 1.93 AC.
6. 6.	24 HOUR CONTACT: BRANDON HARP, (770) 789-2123
	MINIMUM LOT SIZE - 2 ACRES (87,120 SF) FRONT SETBACK: MAJOR STREET = 40 / 100 FT, MINOR STREET = 40 / 65 FT SIDE SETBACK: 30 FT STREET SIDE SETBACK: MAJOR STREET = 40 / 100 FT, MINOR STREET = 40 / 65 FT REAR SETBACK: 40 FT MINIMUM BLDG LINE WIDTH:200 FT MINIMUM LOT FRONTAGE: 200 FT MINIMUM LOT DEPTH: 200 FT PRINCIPLE BUILDING HEIGHT: 35 FT ACCESSORY BUILDING HEIGHT: 35 FT MAXIMUM BUILDING COVERAGE 60% (LOT) BASE/MAXIMUM FLOOR AREA RATIO: 0.30 / 0.50 DISTANCE BETWEEN BUILDINGS: 25 FT
7.	LANDSCAPE STRIPS: 10 FT PERIMETER
8.	VEHICLE STORAGE SUMMARY: TOTAL REQUIRED: OFFICE: 1/250 SQ. FT. OF GFA = 6,400 SQ. FT. GFA = 26 SPACES SHOP/WAREHOUSE: 0.25/1000 SQ. FT. = 4,000 SQ FT = 1 SPACES TOTAL = 27 SPACES
	TOTAL PROVIDED = 27 SPACES (1 HANDICAP SPACES)
9.	EXISTING UTILITY LOCATIONS SHOWN ARE GENERALLY SCHEMATIC IN NATURE AND MAY NOT ACCURATELY REFLECT THE SIZE AND LOCATION OF EACH PARTICULAR UTILITY. CONTRACTOR SHALL FIELD VERIFY LOCATION OF ALL EXISTING UTILITIES PRIOR TO BEGINNING CONSTRUCTION. ALL EXISTING UTILITIES MAY NOT BE SHOWN ON THESE DRAWINGS. IT IS THE CONTRACTORS RESPONSIBILITY TO COORDINATE HIS OPERATIONS WITH ALL UTILITIES WHICH MAY BE IN CONFLICT WITH HIS WORK. THE CONTRACTOR MUST MAINTAIN AND PROTECT ALL SUCH UTILITIES, OR RELOCATE UTILITIES AS NEEDED.
10.	ALL WORK SHALL CONFORM TO THE CITY OF NEWNAN STANDARDS AND SPECIFICATIONS. IT IS THE CONTRACTORS RESPONSIBILITY TO NOTIFY THE PROPER OFFICIALS FOR ANY REQUIRED INSPECTIONS.
11.	A PORTION OF THIS PROPERTY IS LOCATED WITHIN A FLOOD HAZARD AREA ACCORDING TO F.E.M.A. FLOOD INSURANCE RATE MAP FOR COWETA COUNTY COMMUNITY PANEL #13077C0143D DATED FEB. 6, 2013.
12.	STATE WATERS ARE PRESENT ON OR WITHIN 200 FT OF THIS PROJECT SITE.HOWEVER, THEY WILL NOT BE AFFECTED BY CONSTRUCTION ACTIVITIES.
13.	WETLANDS DO NOT EXIST ON THE SITE BUT ARE NOT EFFECTED BY SITE DEVELOPMENT.
14.	HIGHLAND LAND PLANNING LLC DOES NOT ACCEPT RESPONSIBILITY FOR THE DESIGN, PERMITTING, OR INSPECTION OF ANY RETAINING WALLS. CONTRACTOR TO COORDINATE WITH THE DEVELOPER ON DESIGN AND PERMITTING.
15.	CIVIL PLANS DEPICT APPROXIMATE LOCATIONS OF STRUCTURES. CONTRACTOR SHALL UTILIZE ARCHITECTURAL PLANS TO LAYOUT ALL BUILDINGS, INCLUDING SITE WORK REQUIRING SPECIAL DETAILS ON ARCHITECTURAL PLANS. ANY SIGNIFICANT DEVIATION BETWEEN ARCHITECTURAL PLANS AND CIVIL LAYOUT SHOULD BE REPORTED TO THE SITE CIVIL ENGINEER AS SOON AS POSSIBLE.
16.	ANY DAMAGES THAT MAY OCCUR TO REAL PROPERTY OR EXISTING IMPROVEMENTS SHALL BE RESTORED BY THE CONTRACTOR TO AT LEAST THE SAME CONDITION THAT THE REAL PROPERTY OR EXISTING IMPROVEMENTS WERE IN PRIOR TO THE DAMAGES. THIS RESTORATION SHALL BE SUBJECT TO THE OWNER'S APPROVAL; MOREOVER, THIS RESTORATION SHALL NOT BE A BASIS FOR ADDITIONAL COMPENSATION TO THE CONTRACTOR. RESTORATION SHALL INCLUDE, BUT NOT BE LIMITED TO, REGRASSING, REVEGETATION, REPLACING FENCES, REPLACING TREES, ETC.
17.	LOCAL PEDESTRIAN AND VEHICULAR TRAFFIC SHALL BE MAINTAINED AT ALL TIMES. ALL TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. BARRICADING AND TRAFFIC CONTROL DURING CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL CONFORM TO THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" AND GADOT STANDARD SPECIFICATIONS AND DRAWINGS. TRAFFIC FLOW AND ACCESS SHALL BE MAINTAINE DURING ALL PHASES OF THE CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING TRAFFIC SAFETY MEASURES FOR WORK ON PROJECT.
18.	THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, AND PROCEDURES AND SHALL AT ALL TIMES TAKE ALL REASONABLE SAFETY PRECAUTIONS FOR THE SAFETY OF ITS EMPLOYEES ON THE PROJECT AND SHALL COMPLY WITH ALL APPLICABLE PROVISIONS OF FEDERAL, STATE, AND MUNICIPAL SAFETY LAWS AND BUILDING CONSTRUCTION CODES.
19.	CONTRACTOR SHALL MAINTAIN DRAINAGE AT ALL TIMES DURING CONSTRUCTION. PONDING OF WATER IN STREETS, DRIVES, TRUCK COURTS, TRENCHES, ETC. WILL NOT BE ALLOWED.
20.	CONTRACTOR IS RESPONSIBLE FOR COORDINATION WITH UTILITY COMPANIES AND ADJUSTMENT OF EXISTING SANITARY SEWER CLEANOUTS, WATER METERS AND ANY OTHER APPURTENANCES TO FINAL GRADE AS REQUIRED.
21.	CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL
22.	STORM WATER POLLUTION PREVENTION LAWS AND ORDINANCES. THE CONTRACTOR IS FULLY RESPONSIBLE FOR MAINTAINING OPERATIONS THAT MEET OR EXCEED ANY LOCAL, STATE OR FEDERAL PERMIT REQUIREMENTS. ANY PERMIT VIOLATION OR VIOLATIONS OF STATE LAWS AND REQUIREMENTS ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
23.	LAWS AND REQUIREMENTS ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. CONTRACTOR SHALL COMPLY TO THE FULLEST EXTENT WITH THE LATEST STANDARDS OR OSHA DIRECTIVES OR ANY OTHER AGENCY HAVING JURISDICTION FOR EXCAVATION AND TRENCHING PROCEDURES. THE CONTRACTOR SHALL PROVIDE SUPPORT SYSTEMS, SLOPING, BENCHING AND OTHE MEANS OF PROTECTION. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO, ACCESS AND EGRESS FROM AL

CRITERIA FOR OSHA.

- ACTIVITY.
- CONSTRUCTION FACILITIES DURING CONSTRUCTION.
- PRESENTLY IN EFFECT.

DEMOLITION NOTES

- IN COMPLIANCE WITH ALL FEDERAL, STATE AND LOCAL LAWS.

- C100 FOR LOCATION OF TREE PROTECTION FENCING.

GRADING/CONSTRUCTION NOTES:

- 5. SEE SHEETS C500 C530 FOR SITE EROSION CONTROL MEASURES.
- 6. CLEARING LIMITS DETAILED ON THE TREE PROTECTION PLAN.
- NOTED.

UTILITY NOTES

- CONTACT SCOTT TOLAR, (770)301-0245.
- SHALL BE C900.
- CONSTRUCTION.
- FROM THE TRANSFORMER OR LOCAL UTILITY TO THE BUILDING.
- FROM THE LOCAL UTILITY TO THE BUILDING.
- UTILITIES DURING CONSTRUCTION.
- CRITERIA FOR OSHA.
- WITH PUSH ON OR MECHANICAL JOINTS.

- 11. ALL WATER PIPE 3" AND SMALLER SHALL BE PVC SCH 80.
- DOMESTIC METER PROVIDED BY CITY.
- 14. THE MINIMUM HORIZONTAL SEPARATION BETWEEN THE CLOSEST TWO POINTS OF WATER AND SEWER LINE IS TEN FEET (10'). THE MINIMUM VERTICAL SEPARATION BETWEEN THE CLOSEST TWO (18"). 15. EXISTING UTILITY LOCATIONS ARE APPROXIMATE AND SHOULD
- 16. ALL ELECTRIC. TELEPHONE AND GAS LINES. INCLUDING SERVICE LINES. SHALL BE CONNECTED AND

EXCAVATION AND TRENCHING. CONTRACTOR IS RESPONSIBLE TO COMPLY WITH PERFORMANCE

24. THE UTILITY PROTECTION AGENCY IS TO BE NOTIFIED 72 HOURS PRIOR TO ANY LAND DISTURBANCE

25. CONTRACTOR TO COORDINATE WITH POWER COMPANY PROVIDING TEMPORARY SERVICE FOR

26. CONTRACTOR IS TO COMPLY WITH ALL LOCAL BUILDING CODES AND REGULATIONS WHICH ARE

27. SIGNS SHALL BE PERMITTED THRU PLANNING AND ZONING DEPARTMENT.

28. ALL DIMENSIONS ARE TO FACE OF CURB, UNLESS OTHERWISE NOTED. DIMENSIONS OF LANDSCAPE AREAS SHOW CLEAR SPACE, AND ARE TYPICALLY BACK OF CURB UNLESS OTHERWISE NOTED.

29. ALL SITE LIGHTING TO BE BUILDING MOUNTED. NO PARKING LOT POLES REQUIRED

1. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION AND COST OF THE RELOCATION OF ALL UTILITIES ON SITE ASSOCIATED WITH THE CONSTRUCTION OF THIS PROJECT, SUCH AS, BUT NOT LIMITED TO DRAINAGE STRUCTURES, TRAFFIC SIGNS, UTILITY POLES, GUY WIRES, ETC.

2. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL OF ALL DEBRIS AS ACCEPTABLE TO THE OWNER

CONTRACTOR IS RESPONSIBLE FOR REPAIRS OF DAMAGE TO ANY EXISTING IMPROVEMENTS DURING CONSTRUCTION, SUCH AS, BUT NOT LIMITED TO, DRAINAGE, UTILITIES, PAVEMENT, STRIPING, CURBS, ETC. REPAIRS SHALL BE EQUAL TO OR BETTER THAN EXISTING CONDITIONS.

4. ALL AREAS NOTED ON SHEET C100 SHALL BE DEMOLISHED AND REMOVED FROM THE SITE AFTER THE INSTALLATION OF EROSION CONTROL MEASURES AND PRIOR TO BEGINNING SITE WORK. CONTRACTOR SHALL COORDINATE DEMOLITION WITH OTHER SHEETS IN THIS PACKAGE. ITEMS REQUIRING DEMOLITION BASED ON NEW CONSTRUCTION AND NOT DETAILED ON THIS SHEET SHALL ALSO BE REMOVED BY CONTRACTOR IN ACCORDANCE WITH DEMOLITION REQUIREMENTS.

SAWCUT EDGES OF ASPHALT DEMOLITION. PATCH AND REPAIRAS NECESSARY.

COMPLETELY REMOVE TREES EFFECTING NEW WORK ONLY. CONTRACTOR WILL BE REQUIRED TO REPLACE TREES TAKEN OUT THAT ARE NOT IN CONFLICT WITH SITE IMPROVEMENTS. REFER TO SHEET

1. ALL CONTOURS ON PAVEMENT, OR ELSEWHERE, ARE TOP OF FINISHED PAVEMENT OR SURFACE.

2. SLOPES AND DISTURBED AREAS NOT COVERED BY PAVEMENT SHALL BE GRADED SMOOTH AND RECEIVE 4 INCHES OF TOPSOIL. CONTRACTOR TO PROVIDE TOPSOIL IF NOT AVAILABLE ON SITE. THE AREAS SHALL BE SEEDED AND COVERED WITH MATTING AS DESIGNATED ON EROSION CONTROL FERTILIZED AND WATERED TO PROVIDE A HEARTY, MOWABLE STAND OF GRASS. SMALL ROCKS AND DEBRIS MUST BE REMOVED. ISLANDS TO BE BACKFILLED TO TOP OF CURB WITH TOPSOIL AND GRADED TO DRAIN.

3. EARTHWORK SHALL BE ON AN UNCLASSIFIED BASIS. IMPORTING AND EXPORTING OF SOIL MAY BE REQUIRED TO RAISE/LOWER SITE TO FINAL GRADES.

4. MAXIMUM SLOPES ON CUT OR FILL SECTIONS SHALL NOT EXCEED 2:1 UNLESS OTHERWISE NOTED.

7. HDPE (HIGH DENSITY POLYETHYLENE) SHALL BE USED FOR ALL STORM PIPING UNLESS OTHERWISE

WATER SERVICE PROVIDED BY NEWNAN UTILITIES, LOCATED AT 70 SEWELL RD, NEWNAN, GEORGIA. NEWNAN UTILITIES STANDARD SPECIFICATIONS SHALL APPLY TO ALL WATER CONSTRUCTION.

2. SEWER SERVICE PROVIDED BY NEWNAN UTILITIES, LOCATED AT 70 SEWELL RD, NEWNAN, GEORGIA,

2. ALL FIRE SERVICE WATER PIPE SHALL BE C900 UNLESS OTHERWISE INDICATED HEREIN. ALL DOMESTIC WATER SERVICE PIPE 3-INCHES AND SMALLER SHALL BE PVC SCH 80. LARGER DOMESTIC SERVICE PIPE

NEWNAN UTILITIES STANDARD SPECIFICATIONS AND DETAILS SHALL GOVERN ALL WATER

4. THE BUILDING CONTRACTOR IS RESPONSIBLE FOR LOCATION, SIZE AND SPECIFICATIONS OF ALL ELECTRICAL PADS FROM THE LOCAL POWER COMPANY AND PROVIDING SERVICE

THE BUILDING CONTRACTOR IS RESPONSIBLE FOR LOCATION, SIZE AND SPECIFICATIONS OF ALL TELEPHONE PEDESTALS FROM THE LOCAL UTILITY COMPANY AND PROVIDING SERVICE

CONTRACTOR SHALL COORDINATE ANY DISRUPTIONS TO EXISTING UTILITY SERVICES WITH ADJACENT PROPERTY OWNERS AND IS RESPONSIBLE FOR REPAIRS OF DAMAGE TO ANY EXISTING

CONTRACTOR SHALL COMPLY TO THE FULLEST EXTENT WITH THE LATEST STANDARDS OR OSHA DIRECTIVES OR ANY OTHER AGENCY HAVING JURISDICTION FOR EXCAVATION AND TRENCHING PROCEDURES. THE CONTRACTOR SHALL PROVIDE SUPPORT SYSTEMS, SLOPING, BENCHING AND OTHER MEANS OF PROTECTION. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO, ACCESS AND EGRESS FROM ALL EXCAVATION AND TRENCHING. CONTRACTOR IS RESPONSIBLE TO COMPLY WITH PERFORMANCE

SANITARY SEWER PIPE SHALL BE PVC SDR 26 ASTM 3034 FOR PIPES LESS THAN 16' DEEP AND GREATER THAN 4' DEEP UNLESS OTHERWISE NOTED. PVC PIPE SHALL BE BELL AND SPIGOT TYPE WITH INTEGRAL BELL AND RUBBER GASKETS. ALL OTHER PIPE SHALL BE DUCTILE IRON CLASS 50 AWA C150, ANSI: A21.S1

9. ALL SANITARY SEWER LATERALS SHALL BE PVC SDR26 AND SIZED AT 6-INCH MINIMUM. LATERALS SHALL BE INSTALLED AT A MINIMUM 1% SLOPE. SEE PLUMBING PLANS FOR CONTINUATION AT BUILDING.

10. ALL CONNECTIONS TO STRUCTURES REQUIRE KOR-N-SEAL OR EQUAL RUBBER BOOTS.

12. CONTRACTOR SHALL MAINTAIN A MINIMUM OF 4' COVER OVER ALL SEWER AND WATER LINES.

13. CONTRACTOR SHALL COORDINATE INSTALLATION OF WATER SERVICE WITH NEWNAN UTILITIES.

POINTS OF THE WATER AND SEWER LINES IS EIGHTEEN INCHES

BE VERIFIED FOR LOCATION AND NUMBER BY THE CONTRACTOR.

INSTALLED BY THE CONTRACTOR. THIS INCLUDES ANY PERMITTING OR CONNECTION FEES THAT MAY BE REQUIRED, ALL UTILITIES TO BE CONSTRUCTED IN ACCORDANCE WITH THE APPROPRIATE UTILITY COMPANIES SPECIFICATIONS.

- 17. ALL WATER AND SEWER LINES ARE TO BE LOCATABLE BY USE OF WIRE OR DETECTABLE TAPE.
- 18. FOR ALL UTILITY CROSSINGS UNDER EXISTING ROADS, USE DIRECTIONAL BORE OR JACK AND BORE UNLESS APPROVED BY THE CITY ENGINEER. IF PAVEMENT CUTS ARE PROPOSED PROVIDE DETAIL FOR APPROVAL BY THE CITY ENGINEER.
- 17. CONTRACTOR IS RESPONSIBLE FOR LOCATION AND PROTECTION OF ALL EXISTING UTILITIES. ANY ACCIDENTAL BREAKS OR INTERRUPTIONS IN SERVICE TO EXISTING UTILITIES, WHETHER DETAILED ON THESE DRAWINGS OR NOT, SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR WORKING AROUND ALL UTILITIES, INCLUDING NOTIFYING ENGINEER OF ANY CONFLICTS BETWEEN NEW AND EXISTING UTILITIES PRIOR TO INSTALLATION.
- 18. CONTRACTOR MUST PROVIDE PROPER TRAFFIC CONTROL DEVICES FOR CONSTRUCTION AT THE DRIVEWAY CONNECTION AT STILLWOOD DRIVE AND NEWNAN CROSSING BOULEVARD IN ACCORDANCE WITH MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (LATEST ED.).

SIGNING AND MARKING NOTES:

- 1. ALL PAVEMENT MARKINGS AND SIGNAGE SHALL MEET THE LATEST ADA, MUTCD, GDOT AND GA CODE.
- 2. ALL PAVEMENT MARKINGS WITHIN THE RIGHT OF WAY, STRIPES, ARROWS, WORDS, ETC., SHALL BE HOT APPLIED THERMOPLASTIC AND ALL SIGNS SHALL BE HIP UNLESS INDICATED OTHERWISE.
- ALL STANDARD HIGHWAY SIGNS SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH THE DETAILS SHOWN IN THE PLANS, THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, CURRENT EDITION, THE GEORGIA STANDARD SPECIFICATIONS, SUPPLEMENTAL SPECIFICATIONS, AND/OR SPECIAL PROVISIONS.
- 4. CONTRACTOR SHALL ERADICATE ALL STRIPING IN CONFLICT WITH THE TRAFFIC FLOW PLAN. UTILIZE BLASTING, SUCH AS SAND BLASTING OR WATER BLASTING, GRINDING, OR OTHER APPROVED METHODS TO COMPLETE REMOVE PAVEMENT MARKINGS WITHOUT MATERIALLY DAMAGING THE PAVEMENT SURFACE OR TEXTURE. REPAIR (AT THE CONTRACTOR'S EXPENSE) DAMAGE TO THE PAVEMENT OR OTHER SURFACE FROM REMOVING THE MARKINGS.
- 5. ALL SIGNS SHALL BE MOUNTED 7' ABOVE GRADE.
- 6. STOP SIGNS MUST BE BREAK-A-WAY MOUNTED ON A SQUARE TUBE. ALL OTHER SIGNS MAY BE MOUNTED ON U-CHANNEL.


SOIL & EROSION CONTROL NOTES:

- 1. 24 HOUR CONTACT: BRANDON HARP, (770) 789-2123
- 2. TOTAL DISTURBED AREA = 3.90
- 3. THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.
- 4. EROSION CONTROL MEASURES MUST BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- ALL EROSION CONTROL MEASURES ARE TO CONFORM TO THE STANDARDS SET FORTH IN THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" LATEST EDITION.
- EROSION CONTROL DEVICES SHALL BE INSTALLED BEFORE GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DEVELOPER IMMEDIATELY!!
- ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.
- 8. SEDIMENT CONTROL MEASURES MUST BE INSTALLED BEFORE CLEARING AND GRADING BEGINS.
- INSPECTIONS BY CERTIFIED PERSONNEL PROVIDED BY PRIMARY PERMITEE AND THE ASSOCIATED RECORDS SHALL BE KEPT ON SITE IN COMPLIANCE WITH NPDES PERMIT NUMBER GAR 100001.
- 10. DISTURBED AREAS TO BE STABILIZED WITH MULCH WHERE SLOPES EXCEED 3%.
- 11. INSPECTION AND REPAIR OF EROSION CONTROL MEASURES IS REQUIRED ONCE A WEEK AND AFTER EACH RAIN EVENT. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- 12. THE CONSTRUCTION OF THE SITE WILL INITIATE WITH THE INSTALLATION OF EROSION CONTROL MEASURES SUFFICIENT TO CONTROL SEDIMENT DEPOSITS AND EROSION. ALL SEDIMENT CONTROL WILL BE MAINTAINED UNTIL ALL UPSTREAM GROUND WITHIN THE CONSTRUCTION AREA HAS BEEN COMPLETELY STABILIZED WITH PERMANENT VEGETATION AND ALL ROADS/DRIVEWAYS HAVE BEEN PAVED.
- 13. EROSION CONTROL DEVICES SHALL BE INSTALLED BEFORE GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM SHOWN ON THE APPROVED PLANS IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION.
- 14. ALL SILT BARRIERS MUST BE PLACED AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL BE DONE UNTIL SILT BARRIER IS INSTALLED.
- 15. CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL MEASURES UNTIL PERMANENT VEGETATION HAS BEEN ESTABLISHED. CONTRACTOR SHALL CLEAN OUT ALL SEDIMENT COLLECTION AREAS WHEN REQUIRED BY THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" 5TH ED. OR THE CITY OF NEWNAN.
- 16. CONTRACTOR SHALL INSPECT EROSION CONTROL MEASURES AT THE END OF EACH WORKING DAY TO ENSURE MEASURES ARE FUNCTIONING PROPERLY. FAILURE TO INSTALL, OPERATE OR MAINTAIN ALL EROSION CONTROL MEASURES WILL RESULT IN CONSTRUCTION BEING STOPPED ON THE JOB SITE UNTIL SUCH MEASURES ARE CORRECTED TO CITY OF NEWNAN STANDARDS.
- 17 A COPY OF THE APPROVED LAND DISTURBANCE AND NPDES PERMIT SHALL BE PRESENT ON THE JOB SITE WHENEVER LAND DISTURBANCE ACTIVITY IS IN PROGRESS.
- 18. PROVIDE CONSTRUCTION EXIT AS SHOWN ON PLANS AND MAINTAIN DURING CONSTRUCTION.
- 19. NEWNAN ONLY ALLOWS THE USE OF TYPE C SILT FENCE OR APPROVED TYPE C ALTERNATIVE. SILT FENCE HAS A USEFUL LIFE OF SIX MONTHS GENERALLY.
- 20. NO ALTERNATIVE BMP'S WERE USED IN THE DESIGN OF THE ES&PC PLAN.
- 21. NO CONSTRUCTION ACTIVITY WILL DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS, ANY PORTION OF A BIOTA IMPAIRED STREAM SEGMENT.

TREE PROTECTION NOTES:

1. CONTACT THE PLANNING DEPARTMENT AT (770) 254-2354 TO ARRANGE A PRE-CONSTRUCTION

				e Apr
CONFERENCE WITH THE CITY LANDSCAPE ARCHITECT PRIOR TO ANY LAND DISTURBANCE.				5/6/24 Date
ALL TREE PROTECTION MEASURES SHALL BE INSTALLED AND INSPECTED PRIOR TO THE START OF ANY LAND DISTURBANCE AND MAINTAINED UNTIL FINAL LANDSCAPING IS INSTALLED. CALL THE PLANNING DEPARTMENT AT (770) 254-2354 FOR AN INSPECTION BY THE CITY LANDSCAPE ARCHITECT.				
NO PARKING, STORAGE, OR ANY OTHER CONSTRUCTION ACTIVITIES ARE TO OCCUR WITHIN TREE PROTECTION AREAS.				
REFER TO STANDARDS IN GENERAL SPECIFICATIONS FOR TREE PROTECTION.				keview
DIAMETER OF PROTECTION ZONE SHOULD BE ONE FOOT FOR EACH INCH OF TRUNK DIAMETER BREAST HEIGHT OR 1/2 HEIGHT OF TREE, WHICHEVER IS GREATER, UNLESS OTHERWISE NOTED HEREIN. FOR 2-INCH CALIPER TREES OR SMALLER, THE PROTECTION ZONE SHALL BE 6 FOOT MINIMUM DIAMETER.				ISSUED FOR REVIEW Description
TEMPORARY FENCING (4 FT HIGH) SHALL BE PLACED AT THE DRIPLINE OF THE TREE TO BE SAVED. FENCE SHALL COMPLETELY ENCIRCLE THE TREE(S). TO INSTALL FENCE POSTS, AVOID DRIVING POSTS OR STAKES INTO MAJOR ROOTS.	хq			1. Rev
DEAD TREES, SCRUB, OR UNDERGROWTH SHALL BE CUT FLUSH WITH ADJACENT GRADE. THERE WILL BE NO SOIL DISTURBANCE UNDER THE DRIP LINE OF TREES TO BE PRESERVED.	Check RKA			
PLACE 6 INCHES OF BARK MULCH AT AREAS NOT PROTECTED BY BARRIER.				
TREATMENT OF ROOTS EXPOSED DURING CONSTRUCTION: FOR ROOTS OVER 1 INCH IN DIAMETER DAMAGED DURING CONSTRUCTION, MAKE A CLEAN STRAIGHT CUT TO REMOVE DAMAGED PORTION OF ROOT. ALL EXPOSED ROOTS SHOULD BE TEMPORARILY COVERED WITH DAMP BURLAP AND COVERED WITH SOIL OR MULCH AS SOON AS POSSIBLE TO PREVENT DRYING. FOR PRUNING GUIDELINES, SEE ANSI #300.	te: 6/24			
CONSTRUCTION ENTRANCE, ROADS AND UTILITIES SHALL AVOID CRITICAL ROOT ZONES.				
SEE SHEETS C510 - C530 FOR SITE EROSION CONTROL MEASURES				
ESSIBLE ROUTE NOTES (EXTERIOR)		C LL		
MAXIMUM CROSS SLOPE OF ACCESSIBLE ROUTES, SIDEWALKS, AND HANDICAP PARKING STALLS AND ACCESS AISLES SHALL NOT EXCEED A SLOPE OF 2% (1/50).				
THE MAXIMUM RUNNING SLOPE OF ACCESSIBLE ROUTE ALONG SIDEWALKS SHALL NOT EXCEED A SLOPE OF 5% (1:20). SEE RAMP NOTES BELOW.		IV d.		
MINIMUM CLEAR WIDTH IS 3'. IF ACCESSIBLE ROUTE HAS LESS THAN 5' CLEAR WIDTH, THEN PASSING SPACES AT LEAST 5'X5' SHALL BE LOCATED EVERY 200' OR LESS INTERSECTING SIDEWALKS MEET THIS REQUIREMENT. LONGITUDINAL (RUNNING) SLOPE MAY NOT EXCEED 5% UNLESS RAMP IS INSTALLED (RAMPS MAY NOT EXCEED 8.33%). CROSS SLOPE MAY NOT EXCEED 2%. GAPS IN ROUTE MAY NOT EXCEED 1/2" IN WIDTH.		GENIE		
FINISHED SURFACE HEIGHT DIFFERENCE REQUIREMENTS: - 0 TO 1/4": NO REQUIREMENTS - 1/4" TO 1/2": BEVEL WITH 1:2 SLOPE - LARGER THAN 1/2": CONFORM TO REQUIREMENTS FOR RAMP	┝			
RAMPS: MAX RAMP SLOPE 8.33% (1:12). RAMPS STEEPER THAN 8.33% ARE NOT ACCEPTABLE. MAX RISE FOR ANY RAMP RUN IS 30" (AT 8.33% SLOPE, MAXIMUM RUN OF RAMP IS 30') MAX CROSS SLOPE OF RAMP 2% (1:50)				TV GEORGIA
LANDINGS: RAMPS SHALL HAVE LEVEL LANDINGS AT BOTTOM AND TOP OF EACH RAMP. LANDING SHALL BE AT LEAST AS WIDE AS RAMP LEADING TO IT. LANDING LENGTH SHALL BE MINIMUM 5' CLEAR IF RAMPS CHANGE DIRECTION AT LANDING, MINIMUM LANDING SIZE SHALL BE 5'X5'. ALL LANDINGS ARE TO BE NO MORE THAN 2% SLOPE IN ANY DIRECTION.	SI	ر ۲	FERS	
HANDRAILS: HANDRAILS REQUIRED ON BOTH SIDES (MIN. 36" CLEAR BETWEEN HANDRAILS) WHEN RAMP RISE IS GREATER			JAR	
PROVIDE MINIMUM 12" LONG HANDRAIL EXTENSION AT TOP AND BOTTOM LANDINGS. PROVIDE MINIMUM 2" HIGH EDGE PROTECTION OR RAIL WITH LESS THAN 4" CLEAR TO RAMP IF RAMP HAS	DMEN	RAC RAC	DQI	
DROP-OFFS. ROUTES BETWEEN BUILDINGS WITH ONLY DWELLING UNITS DO NOT HAVE TO HAVE HANDRAILS. STAIRS NOT ALLOWED AS PART OF ACCESSIBLE ROUTE BUT IF ADJACENT TO ROUT OR PART OF TENANT SPACE MUST MEET REQUIREMENTS FOR STAIR RAILS.	DEVELOI	CONT	D HEA	
CURB RAMPS: MAX SLOPE OF CURB RAMP 8.33%.	SITE	B2	JRL]	TUE ETU
MAX SLOPE OF SIDE FLARES 10%. MAX SLOPE OF ADJOINING GUTTERS, ROAD SURFACE, OR ACCESSIBLE ROUTE 5%. MIN WIDTH 36" (NOT INCLUDING SIDE FLARES). DETECTABLE WARNING IS REQUIRED ON CURB RAMPS IN PUBLIC RIGHTS OF WAY, AND SHALL BE 24" MINIMUM IN THE DIRECTION OF TRAVEL AND EXTEND THE FULL WIDTH OF THE CURB RAMP OR FLUSH SURFACE. DETECTABLE WARNINGS SHALL BE LOCATED SO THE EDGE NEAREST THE CURB LINE IS 6" TO 8" FROM THE CURB LINE.			M	73 AND 74 OF
PARKING SPACES MINIMUM 8' WIDE ACCESSIBLE PARKING SPACE				
MINIMUM 8 WIDE ACCESSIBLE PARKING SPACE MINIMUM 5' WIDE ACCESS AISLE AT STANDARD SPACES MINIMUM 8' WIDE ACCESS AISLE AT VAN ACCESSIBLE SPACES MAXIMUM 2% (1:50) SLOPE IN ANY DIRECTION			_	-
<u>SIGNAGE</u> ACCESSIBLE PARKING SPACES SHALL BE DESIGNATED AS RESERVED BY A SIGN SHOWING THE SYMBOL OF ACCESSIBILITY. VAN ACCESSIBLE SPACES SHALL HAVE AN ADDITIONAL SIGN "VAN-ACCESSIBLE" MOUNTED BELOW THE SYMBOL. SUCH SIGNS SHALL BE LOCATED SO THEY CANNOT BE OBSCURED BY A VEHICLE PARKED IN THE SPACE (7' ABOVE GRADE UNLESS OTHER HEIGHT REQUIRED BY LOCAL JURISDICTION).			C E R K S	R
PAVEMENT MARKINGS: AS REQUIRED BY LOCAL JURISDICTIONAL AUTHORITY (RECOMMENDED CROSSWALK MARKING TO DESIGNATE ACCESSIBLE PEDESTRIAN ROUTE)	K		BIONAL)* 8)
ACCESSIBLE ROUTES	-IC	К.	AL	-
	REVERSION AREAS REFER TO STANDARDS IN GENERAL SPECIFICATIONS FOR THE PROTICITION REFERENCE OF PROTECTION ZONE SHALL BE CONFIDENCE TO THE PROTICITION UNITED OF PROTECTION ZONE SHALL BE CONFIDENCE TO THE PROTICITION NUMERAL INFORMATION OF THE WINDOWS IN STATUS AND	RETER TO STANDARDS IN GPUERAL SECTIONATIONS FOR THEF RESTOREON. Image: Comparison of the section of the sectio	REFER TO STANDARDS AN GENERAL SECONDARION FOR THE PROTECTION. REFER TO STANDARDS AN GENERAL SECONDARION FOR THE PROTECTION. REFER TO STANDARDS AN GENERAL SECONDARION FOR THE PROTECTION. REFER TO STANDARDS AN GENERAL SECONDARION FOR THE PROTECTION. REFER TO STANDARDS AN GENERAL UNDER STANDARDS SECONDARIS AND CONTRACT TO PROVIDE THE PROTECTION CONTRACT THE REFERSE TO TRANSMITTER AND THE OWNER AND THE THEOREM SOUTH FOR THE OWNER AND THE OWNER AN	PROTECTION MEAN. PROPERTOR MEAN. PROP



CONTACT THE PLANNING DEPARTMENT AT (770) 254-2354 TO ARRANGE A PRE-CONSTRUCTION CONFERENCE WITH THE CITY


2. ALL TREE PROTECTION MEASURES SHALL BE INSTALLED AND INSPECTED PRIOR TO THE START OF ANY LAND DISTURBANCE AND MAINTAINED UNTIL FINAL LANDSCAPING IS INSTALLED. CALL THE PLANNING DEPARTMENT AT (770) 254-2354 FOR AN INSPECTION BY

3. NO PARKING, STORAGE, OR ANY OTHER CONSTRUCTION ACTIVITIES ARE TO OCCUR WITHIN TREE PROTECTION AREAS. 4. A MAINTENANCE INSPECTION OF TREES WILL BE PERFORMED AFTER TWO FULL GROWING SEASONS FROM THE DATE OF THE FINAL CONSTRUCTION INSPECTION. PROJECT OWNERS AT THE TIME OF THE MAINTENANCE INSPECTION ARE RESPONSIBLE FOR ORDINANCE



SURVEY PLAN NOTES:

- A. SEE SHEET C001 FOR ADDITIONAL SITE PLAN NOTES. B. DEMO ALL BRUSH, STRUCTURES, FOOTINGS AND DEBRIS PILES. DEMO TREES THAT ARE NOT SURROUNDED BY TREE PROTECTION FENCING ONLY AS NECESSARY.
- C. PROPERTY SUMMARY: EXISTING PROPERTY: 8.31 +/- AC (TOTAL)
- D. SURVEY NOTE: GA STATE PLANE, WEST ZONE, NAD 83 E. A PORTION OF THIS PROPERTY IS LOCATED WITHIN A FLOOD HAZARD AREA ACCORDING TO F.E.M.A. FLOOD INSURANCE RATE MAP FOR COWETA COUNTY
- COMMUNITY PANEL #13077C0143D DATED FEB. 6, 2013. F. NO WETLANDS, BUT STATE WATERS ARE PRESENT ON SITE, OR WITHIN 200 FEET OF THE PROPOSED DEVELOPMENT, BUT NOT AFFECTED BY THE PROPOSED DEVELOPMENT
- G. CONTRACTOR SHALL PLACE TREE SAVE FENCE AROUND PROTECTED AREAS NOTED PRIOR TO LAND DISTURBANCE ACTIVITIES. CONTACT CITY OF NEWNAN FOR APPROVAL PRIOR TO PROCEEDING. SEE ADDITIONAL NOTES THIS PAGE AND LANDSCAPE PLANS FOR ADDITIONAL INFORMATION.




DRAWING NO.


C100

SURVEY PLAN LEGEND :

	=	PROPERTY LINE
	=	SETBACK
-00	=	TREE PROTECTION FENCE
	=	LIMITS OF DEMOLITION
$\equiv \equiv \equiv \equiv \equiv \equiv$	=	EXISTING ROAD
	=	EXIST. CONTOURS
V	=	EXISTING FIRE HYDRANT
\bowtie	=	EXISTING WATER VALVE
-Ċ-	=	EXISTING LIGHT POLE







GRADING / DRAINAGE NOTES


- 1. SITE PREPARATION: ALL TREES AND UNWANTED VEGETATION SHOULD BE REMOVED, STUMPS GRUBBED AND ORGANIC TOPSOIL STRIPPED.
- 2. ALL AREAS TO RECEIVE STRUCTURAL FILL MATERIAL SHALL BE EVALUATED PRIOR TO FILL PLACEMENT. THE APPROVAL PROCESS SHOULD INCLUDE PROOFROLLING THE SUBGRADE WITH A FULLY LOADED TANDEM AXLE DUMP TRUCK (20 TONS) DURING A PERIOD OF DRY WEATHER AND UNDER THE OBSERVATION OF THE GEOTECHNICAL ENGINEER. DENSIFICATION OF SUBGRADE SOILS MAY BE REQUIRED.
- 3. ALL STRUCTURAL FILL SHOULD BE COMPACTED TO AT LEAST 95 PERCENT OF THE SOIL'S STANDARD PROCTOR MAXIMUM DRY DENSITY, AS DETERMINED BY ASTM STANDARD D-698. THE UPPER FOOT OF FILL WHICH WILL SUPPORT PAVEMENTS OR SLABS SHOULD BE COMPACTED TO AT LEAST 98 PERCENT OF THE SOIL'S STANDARD PROCTOR MAXIMUM DRY DENSITY FOR IMPROVED SUPPORT. IN AREAS WHICH ARE AT OR ABOVE THE FINISHED GRADE, AND WHICH WILL SUPPORT PAVEMENTS OR SLABS, THE UPPER 8 INCHES IMMEDIATELY BELOW THESE SYSTEMS SHOULD BE SCARIFIED AND RECOMPACTED TO THE 98 PERCENT CRITERIA. STRUCTURAL FILL SHOULD BE FREE OF ORGANIC MATERIAL, HAVE A PLASTICITY INDEX (PI) LESS THAN 20 AND CONTAIN ROCK SIZES NO LARGER THAN 4 INCHES.
- 4. DENSITY TESTING SHOULD BE PERFORMED BY A SOILS TECHNICIAN TO DETERMINE THE DEGREE OF COMPACTION AND VERIFY COMPLIANCE WITH THE PROJECT SPECIFICATIONS. FOR UNDERFLOOR AREAS, AT LEAST ONE FIELD DENSITY TEST SHOULD BE MADE PER 5000 SQUARE FEET OF FILL AREA FOR EACH TWO FOOT LIFT. TESTING FREQUENCY SHOULD BE INCREASED IN CONFINED AREAS. AREAS WHICH DO NOT MEET THE COMPACTION SPECIFICATIONS SHOULD BE RECOMPACTED TO ACHIEVE COMPLIANCE. IN CONFINED AREAS, SUCH AS UTILITY TRENCHES, THE USE OF PORTABLE COMPACTION EQUIPMENT AND THIN LIFTS OF 3 TO 4 INCHES MAY BE REQUIRED TO ACHIEVE COMPACTION.
- 5. EARTHWORK SHALL BE ON AN UNCLASSIFIED BASIS. IMPORTING AND EXPORTING OF SOIL MAY BE REQUIRED TO RAISE/LOWER SITE TO FINAL GRADES. EXCAVATIONS MAY BE ACCOMPLISHED USING CONVENTIONAL HEAVY EARTHMOVING EQUIPMENT SUCH AS DOZER ASSISTED PANS, AND SIGNIFICANT EXCAVATIONS OF ROCK AND PARTIALLY WEATHERED ROCK ARE NOT ANTICIPATED.
- 6. PERMANENT AND TEMPORARY SLOPES SHALL BE CONSTRUCTED NO STEEPER THAN 2H: 1V FOR SLOPES LESS THAN 15 FEET HIGH. PERMANENT SLOPES SHOULD BE CONSTRUCTED NO STEEPER THAN 2H: 1V. ALL FINISHED SLOPES SHOULD BE SUITABLY PROTECTED FROM EROSION.
- 7. ALL CONTOURS ON PAVEMENT, OR ELSEWHERE, ARE TOP OF FINISHED PAVEMENT OR SURFACE.
- 8. SLOPES AND DISTURBED AREAS NOT COVERED BY PAVEMENT SHALL BE GRADED SMOOTH AND RECEIVE 4 INCHES OF TOPSOIL. CONTRACTOR TO PROVIDE TOPSOIL IF NOT AVAILABLE ON SITE. THE AREAS SHALL BE SEEDED AND COVERED WITH MATTING AS DESIGNATED ON EROSION CONTROL FERTILIZED AND WATERED TO PROVIDE A HEARTY, MOWABLE STAND OF GRASS. SMALL ROCKS AND DEBRIS MUST BE REMOVED. ISLANDS TO BE BACKFILLED TO TOP OF CURB WITH TOPSOIL AND GRADED TO DRAIN.
- 9. CLEARING LIMITS DETAILED ON THE TREE PROTECTION PLAN.
- 10. EX. GROUNDWATER WELL: ANY WATER WELLS SHALL BE ABANDONED HYDRAULICALLY IN COMPLIANCE WITH GEORGIA LAWS FOR WATER WELLS AS WELL AS "STRUCTURALLY". ONLY A CERTIFIED WATER WELL CONTRACTOR CAN ABANDON WELLS HYDRAULICALLY. UNLESS CEMENT GROUT IS USED FOR WELL ABANDONMENT, WE RECOMMEND THAT ALL WELLS BE STRUCTURALLY PLUGGED WITH CONCRETE PLUG OVERSIZED SO THAT THE PLUG WILL NOT FALL FURTHER INTO THE WELL. THE PLUG SHOULD BE CONSTRUCTED AT LEAST ONE FOOT BELOW FINISH GRADE IN LANDSCAPED AREAS TO FACILITATE GRASSING AND DEEPER IN STRUCTURAL AREAS TO AVOID FOUNDATIONS, UTILITIES, SLABS AND OTHER SIMILAR ITEMS. SPECIFIC RECOMMENDATION FOR STRUCTURAL ABANDONMENT OF THE WELLS CAN BE DETERMINED AT THE TIME OF CONSTRUCTION BY THE GEOTECHNICAL ENGINEER.
- 11. COORDINATE ROOF DRAINAGE PIPING WITH ARCHITECTURAL PLANS FOR DOWNSPOUT LOCATIONS. ALL EXTERIOR ROOF DRAIN PIPE SHALL BE HDPE PIPE AT SIZE SHOWN, PLACED MINIMUM 1% FALL TO NEAREST MANHOLE STRUCTURE. CLEANOUTS SHALL BE PROVIDED AT ALL JUNCTIONS.


DRAINAGE EASEMENT NOTE:

12. THE OWNER OF RECORD, ON BEHALF OF HIMSELF (ITSELF) AND ALL SUCCESSORS IN INTEREST SPECIFICALLY RELEASES THE CITY OF NEWNAN FROM ANY AND ALL LIABILITY AND RESPONSIBILITY FOR FLOODING OR EROSION FROM STORM DRAINS OR FROM FLOODING FROM HIGH WATER OF NATURAL CREEKS, RIVERS OR DRAINAGE FEATURES SHOWN HEREIN. A DRAINAGE EASEMENT IS HEREBY ESTABLISHED FOR THE THE SOLE PURPOSE OF PROVIDING FOR THE EMERGENCY PROTECTION OF THE FREE FLOW OF SURFACE WATERS ALONG ALL WATERCOURSES AS ESTABLISHED BY THE REGULATIONS OF THE CITY OF NEWNAN. THE PUBLIC WORKS DIRECTOR MAY CONDUCT EMERGENCY MAINTENANCE OPERATIONS WITHIN THIS EASEMENT WHERE EMERGENCY CONDITIONS EXIST. EMERGENCY MAINTENANCE SHALL BE THE REMOVAL OF TREES AND OTHER DEBRIS, EXCAVATION, FILLING AND THE LIKE, NECESSARY TO REMEDY A CONDITION, WHICH IN THE JUDGMENT OF THE PUBLIC WORKS DIRECTOR, IS POTENTIALLY INJURIOUS TO LIFE, PROPERTY OF THE PUBLIC ROADS OR UTILITY SYSTEM. SUCH EMERGENCY MAINTENANCE, CONDUCTED FOR THE COMMON GOOD, SHALL NOT BE CONSTRUED AS CONSTITUTING A CONTINUING MAINTENANCE OBLIGATION ON THE PART OF THE CITY OF NEWNAN NOR AN ABROGATION OF THE CITY'S RIGHTS TO SEEK REIMBURSEMENT FOR EXPENSES FROM THE OWNERS OF THE PROPERTY/IES OF THE LANDS THAT GENERATED THE CONDITIONS.

PLAN LEGE	ND :
\bigcirc	= JUNCTION BOX (JB)
_	 STORM PIPE - SEE PROFILES ON SHEET C350 AND PIPE BEDDING DETAIL ON SHEET C703.
900	= EXISTING CONTOURS
<u> </u>	= PROPOSED CONTOURS
\	= PROPOSED LIGHT POLE
TP	= TOP OF PAVING/GUTTER
	= GRADE BREAK
→ ₩-	= FLOW ARROW
(800.45)	= SPOT ELEVATION
-00	= TREE PROTECTION FENCE
• • •	= RETAINING WALL
	= 20 FT STORMWATER ACCESS/MAINTENANCE EASEMENT

www.Georgia811.com





2 YR PIPE CHART SCALE: N.T.S.


25 YR PIPE CHART SCALE: N.T.S.

100 YR PIPE CHART SCALE: N.T.S.


DRAWING NO. C350	SITE DEVELOPMENT PLANS FOR B2 CONTRACTING WORLD HEADQUARTERS	STORM PIPE PROFILES	Date:Drawn by:Check by:5/6/24EAMRKA50'25'0'50'25'0'		ISSUED FOR REVIEW	5/6/24 RKA	
LAND LOTS 73 AND 74 OF THE 5TH DI	LAND LOTS 73 AND 74 OF THE 5TH DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA		SCALE: $1^{*} = 50^{\circ}$	Rev. Description	ion	Date Apr.	







	ENERAL NOTES: OWNER/DEVELOPER - PRIMARY PERMITTEE: (#5) 3. SURVEYOR:	Engineer Certification
	B2 CONTRACTINGW. S. BODKIN SURVEYING, LLC180 WALTER WAY #110315 CAASTLEWOOD RDFAYETTEVILLE, GA 30214TYRONE, GA 30290CONTACT: BRANDON HARPCONTACT: SCOTT BODKIN, R.L.S.EMAIL: BHARP@B2CONTRACTING.COMPHONE: (770) 312-5500PHONE: (770) 789-2123PHONE: (770) 312-5500	"I certify under penalty of law that location described herein by myself "I certify that the permittee's Erosic
2.	ENGINEER - QUALIFIED PROFESSIONAL: HIGHLAND LAND PLANNING 201 PROSPECT PARK, SUITE A PEACHTREE CITY, GA 30269 CONTACT: REID K ALMAND, P.E. PHONE: REID.ALMAND@HIGHLANDLP.US PHONE: (770) 631-0499	provides for an appropriate and cor required by the Georgia Water Qua Erosion and Sediment Control in Ge Conservation Commission as of Jan activity was permitted, provides for sampling of the storm water outfall management practices and samplin contained in the General NPDES Pe
	ROSION, SEDIMENTATION AND DLLUTION CONTROL NOTES:	Design professional of record shall start. The primary permittee shall r start date prior to that start date.
<u> </u>		REID K ALMAND, P.E. P.E. #: •
1.	24-HOUR CONTACT: BRANDON HARP, (770) 789-2123 (EMAIL: BHARP@B2CONTRACTING.COM) (#4)	REID R ALMAND, P.E. P.E. #.
2. 3.	DISTURBED AREA: 3.90 AC.; TOTAL SITE AREA: 8.31 +/- AC.; TOTAL IMPERVIOUS AREA: 0.76 AC. (#6) THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.	
4.	EROSION CONTROL MEASURES MUST BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.	
5.	ALL EROSION CONTROL MEASURES ARE TO CONFORM TO THE STANDARDS SET FORTH IN THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" LATEST EDITION.	
6.	EROSION CONTROL DEVICES SHALL BE INSTALLED BEFORE GROUND DISTURBANCE OCCURS. THE LOCATION OF SOME OF THE EROSION CONTROL DEVICES MAY HAVE TO BE ALTERED FROM SHOWN ON THE APPROVED PLANS. IF DRAINAGE PATTERNS DURING CONSTRUCTION ARE DIFFERENT FROM THE FINAL PROPOSED DRAINAGE PATTERNS, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ACCOMPLISH EROSION CONTROL FOR ALL DRAINAGE PATTERNS CREATED AT VARIOUS STAGES DURING CONSTRUCTION. ANY DIFFICULTY IN CONTROLLING EROSION DURING ANY PHASE OF CONSTRUCTION SHALL BE REPORTED TO THE DEVELOPER IMMEDIATELY!	(#29) (/ ITEM 1 3
7.	ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED $(#21)$ WITH MULCH OR TEMPORARY SEEDING.	CLEARING/DEMO
8.	SEDIMENT CONTROL MEASURES MUST BE INSTALLED BEFORE CLEARING AND GRADING BEGINS.	(SEDIMENT PONDS)
9.	INSPECTIONS BY QUALIFIED PERSONNEL PROVIDED BY PRIMARY PERMITEE AND THE ASSOCIATED RECORDS SHALL BE KEPT ON SITE IN COMPLIANCE WITH NPDES PERMIT NUMBER GAR 100001.	PAVING
10.	THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF (#14) THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPs WITHIN 7 DAYS AFTER INSTALLATION.	TEMP. GRASSING PERM. GRASSING
11.	NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED BY THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.	MAINTENANCE OF ES & PC BMP'S
12.	AMENDMENTS / REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A (#17) HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.	
13.	THE PRIMARY PERMITTEE IS REQUIRED TO KEEP THE ES&PC PLAN UP-TO-DATE.	
14.	STATE WATERS ARE LOCATED ON OR WITHIN 200 FEET OF THE PROJECTS BOUNDARIES.	
15.	WASTE MATERIALS SHALL NOT BE DISCHARGED TO STATE WATERS EXCEPT AS AUTHORIZED BY A (#18) SECTION 404 PERMIT.	
16.	THE ES&PC PLAN IS IN COMPLIANCE WITH ALL CURRENT WASTE DISPOSAL, SANITARY SEWER, AND/OR SEPTIC TANK REGULATIONS.	
17.	EROSION CONTROL MATTING, Ss, IS REQUIRED ON ALL SLOPES 3:1 OR STEEPER.	
18.	GAB SHOULD BE PLACED IN PARKING LOT AREA AND DRIVEWAY AREAS AS SOON AS POSSIBLE FOR CONSTRUCTION TRAFFIC, WORKERS PARKING AND STAGING AREAS.	
19.	NO ALTERNATIVE BMP'S WERE USED IN THE DESIGN OF THE ES&PC PLAN. (#39)	
20.	MAINTENANCE OF ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES, WHETHER TEMPORARY OR PERMANENT SHALL AT ALL TIMES BE THE RESPONSIBILITY OF THE PROPERTY OWNER.	
	VICINITY MAP	
		PREPARED FC



PREPARED FOR:



on (#12)(#13)(#14)

t this plan was prepared after a site visit to the If or my authorized agent, under my supervision.

ion, Sedimentation and Pollution Control Plan omprehensive system of best management practices ality Control Act and the document "Manual for Georgia," (published by the Georgia Soil and Water nuary 1 of the year in which the land-disturbing or the sampling of the receiving water(s) or the Ils and that the designed system of best ng methods is expected to meet the requirements ermit No. GAR 100001."

I inspect the site within 7 days of the construction notify the design professional of the construction

GSWCC#: 79754 17263

	PATED STA	ART DATE -	EDULE MAY 20	24)			
		MONTH					
3	9		12	1	5	18	
1		_				1	

EROSION, SEDIMENTATION AND POLLUTION CONTROL PLANS FOR B2 CONTRACTING WORLD HEADQUARTERS

LAND LOT 73 & 74 OF THE 5th DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA PARCEL ID NUMBER: N57A 001A

#7 **GPS LOCATION OF** THE CONSTRUCTION EXIT LAT: 33.3974668° LONG: -084.7820601°

SITE LOCATION MAP (N.T.S.) (#10)



	5/6/24 RKA Date Apr.
S	Date: Drawn by: Check by: Image: Check by: 5/6/24 EAM RKA Image: Check by: 5/6/24 EAM RKA 1 ISSUED FOR REVIEW 1 ISSUED FOR REVIEW
#8	EROSION CONTROL COVER
	SITE DEVELOPMENT PLANS FOR B2 CONTRACTING WORLD HEADQUARTERS LAND LOTS 73 AND 74 OF THE 5TH DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA
	CLARE CE PROFILIENT
REID K ALMAND, P.E. GA PE #47263 GSWCC LEVEL II #79754	
REORGANGE www.Georgia811.com	drawing no.

(#2)

Site Description and Location:	C. <u>OTHER CONTROLS</u>
THE SITE IS LOCATED ALONG THE EASTERN R/W OF HILLWOOD CIRCLE SOUTH OF THEINTERSECTIONOF HILLWOOD CIRCLE AND MILLARD FARMER INDUSTRIAL BLVD IN THE CITY OF	 Waste disposal. Solid materials, including bui except as authorized by a section 404 permit
NEWNAN, GA. CURRENTLY, THE SITE IS MODERATELY WOODED. IN THE PROPOSED, DEVELOPED CONDITION, THE PROJECT WILL CONSIST OF A TWO-STORY OFFICE AND WAHREHOUSE BUILDING	(2) Off-site vehicle tracking of dirt, solids, and se eliminated to the maximum extent practical.
VITH ASSOCIATED PARKING, UTILITIES, LANDSCAPING AND STORMWATER MANAGEMENT.	(3) The permittee is in compliance with the state regulations.
Construction Site Area:	(4) Petroleum Spills and Leaks a. Best management practices for preve
TE AREA: 8.31 +/- AC STURBED AREA: 3.90 AC.	for leaks and receive regular preventive r products will be stored in tightly sealed c
oil Types: (#47)	stored in tanks will have be surrounded the stored in tanks will have be surrounded the appendix substances used onsite will be appendix substances used onsite will be appendix substances.
E, RK	petroleum products shall be stored and u and shall be located in an area with the l
etlands: (#42) TLANDS ARE NOT LOCATED WITHIN THE BOUNDARIES OF THE PROJECT PROPERTY.	Emergency contact numbers and procedu b. Best management practices for remed
\frown	(#25) (#25) (#25) (#25) (#25) (#26)
te Waters: (#42) E WATERS ARE LOCATED ON OR WITHIN 200 FEET OF THE BOUNDARIES OF THE PROJECT	 and procedures will be made avail Materials and equipment necessar
ERTY BUT WILL NOT BE AFFECTED BY CONSTRUCTION ACTIVITIES.	Typical materials and equipment in gloves, goggles, cat litter, sand, sa
	 Spill prevention practices and proc
S CURRENT STATE, THE SITE DRAINS CONTAINS SIGNIFICANT SLOPES. IT DRAINS FROM TH TO SOUTH AND NATURALLY FLOWS INTO AN UNNAMED TRIBUTARY OF WAHOO CREEK. IN PROPOSED CONDITION, THE EXISTING BASINS WILL BE MAINTAINED AND STORMWATER WILL	 All spills will be cleaned up immed
VAGED BY A SERIES OF ROADSIDE DITCHES AND CULVERTS.	 All spins will be cleaned up infined local, State, and Federal regulation FOR SPILLS THAT IMPACT SURFACE
TATE WATERS BUFFER ENCROACHMENTS ARE PROPOSED. CONSEQUENTLY, NO ER VARIANCES ARE NECESSARY.	NATIONAL RESPONSE CENTER (N 424 - 8802 or 1 - 202 - 426 - 2
	 FOR SPILLS OF AN UNKNOWN AM CONTACTED WITHIN 24 HOURS A
	FOR SPILLS GREATER THAN 25 GA GEORGIA E.P.D. WILL BE CONTACT
	FOR SPILLS LESS THAN 25 GALLO WILL BE CLEANED UP AND LOCAL
DPES After Grading: IMUM CUT AND FILL SLOPES SHALL NOT EXCEED 2H:1V UNLESS OTHERWISE INDICATED.	The contractor shall notify the licens gallons of petroleum is stored onsite
sion Control Measures:	equipment has a capacity greater the Containment and Countermeasurers
ION CONTROL MEASURES STRUCTURAL AND NONSTRUCTURAL CONTROLS WILL BE USED	(NOTE: CONTACT NUMBERS HAVE C
E TO PREVENT EROSION DURING CONSTRUCTION INCLUDING TEMPORARY GRASSING AND STORM DRAIN INLET AND OUTLET PROTECTION, SILT FENCING, SLOPE DRAINS, INLET	CORRECT)
IENT TRAPS, AND OTHER MEASURES AS NECESSARY TO LIMIT SEDIMENT DISCHARGE FROM ITE. PLEASE REFER TO THE EROSION CONTROL PLANS FOR SPECIFIC INFORMATION.	 (5) Product Specific Practices a. Petroleum Based Products - Contai increasted deily for leads and enille
PRIMARY PERMITTEE SHALL MAKE EROSION, SEDIMENTATION AND POLLUTION CONTROL S AVAILABLE UPON REQUEST TO DESIGNATED OFFICIALS OF THE LOCAL GOVERNMENT.	inspected daily for leaks and spills. inspections and regular preventations
ECTIONS SHALL BE DONE BY CERTIFIED PERSONNEL PROVIDED BY THE PRIMARY PERMITTEE THE ASSOCIATED RECORDS SHALL BE KEPT ON-SITE IN COMPLIANCE WITH GAR 100001."	areas will be located away from St In addition, temporary fueling tan
	prevent/minimize site contamination Proper disposal methods will include
	b. Petroleum storage shall be done in
\sim	prevent storm water discharges on a. All petroleum sto
Site Description (#9) (#45)	located under a tem b. All petroleum sto
Existing Site Conditions site currently consists of a moderately wooded parcel.	area. c. Paints/Finishes/Solvents - All produ
oposed Construction Activities proposed development will consist of a multi-story medical office building. The building will be on a pw foundation system, and will have parking and associated utilities.	not in use. Excess product will not product, materials used with these
i. GRADING ii. DRAINAGE	according to manufacturer's specif d. Concrete Truck Washing - NO conc
i PAVING / STORMWATER FACILITIES	concrete or drum wash water onsi e. Fertilizer/Herbicides - These produ
nstruction Sequence	manufacturer's specifications or ab the GSWCC Manual for Erosion and
roposed construction is estimated to take approximately 18 months. Sediment and erosion control will intained for the duration of construction. Perimeter silt fence and the construction exit will be installed	materials will be under roof in seal f. Building Materials - No building or
o clearing of debris. Access to exposed soil will be limited to off-road construction equipment and ruction material.	All such material will be disposed of
he initial 2 weeks of clearing of debris, temporary vegetation will be provided. Rough grading will after clearing, along with structural controls for sediment storage, concrete work and silt fence as	(#27) g. Cover - building materials will be s or lean-to, to ensure no pollution of base. All liquids, solvents, fuels, or
d. Permanent vegetation will be installed within two weeks of completion of grading activities.	ensure no leakage or commingling
refer to the Erosion and Sediment Control Plan, Sheet C500, for the activity schedule.	3. Inspections. $(\#_{30})$
<u>drology</u> ollowing runoff coefficients were calculated for the existing and proposed developed conditions of the	a. Permittee requirements
outing drainage basins. asin A - 8.63 ACS.	(1). Each day when any type of construction activity has taken permittee's site, certified personnel provided by the primary p
isting CN: Basin A - 55 oposed CN: Basin A1 - 4.47; CN: 74.70, Basin A2 - 4.16 ac; CN: 55	where petroleum products are stored, used, or handled for sp the primary permittee's site where vehicles enter or exit the si
Controls	must be conducted until a Notice of Termination is submitted.
	(2). Measure and record rainfall within disturbed areas of the any non-working Saturday, non-working Sunday and non-working compliance with this permit shall be representative of the more
ollowing controls will be implemented at the construction site:	compliance with this permit shall be representative of the mor areas of the site have undergone final stabilization or establis appropriate for the region.
itial perimeter BMP controls will include silt fencing and stone pads to be used at the construction exit. termediate grading and drainage BMPs will include silt fencing, stone pads, and sediment traps to be	(3). Certified personnel (provided by the primary permittee) sl
at the construction exit, and temporary grassing. nal BMPs will include permanent grassing by seed and additional landscaping as necessary.	days and within 24 hours of the end of a storm that is 0.5 incl Friday or on any non-working Saturday, non-working Sunday
sion and Sediment Controls	shall be completed by the end of the next business day and/o primary permittee's construction site; (b) areas used by the p
Stabilization measures. Stabilization measures will be initiated as soon as practicable in portions of	precipitation; and (c) structural control measures. Erosion and primary permittee's site shall be observed to ensure that they
the site where construction activities have temporarily or permanently ceased, but in no case more than 14 days after the construction activity in that portion of the site has temporarily or permanently	accessible, they shall be inspected to ascertain whether eros to receiving water(s). For
ceased. Where the initiation of stabilization measures by the 14th day after construction activity temporarily or permanently ceases is precluded by snow cover or other adverse weather conditions,	areas of a site that have undergone final stabilization or estat perennials appropriate for the region, the permittee must com
stabilization measures shall be initiated as soon as practicable. Where construction activity will resume on a portion of the site within 21 days from when activities ceased, (i.e., the total time period	until a Notice of Termination is submitted. (4). Certified personnel (provided by the primary permittee) sl
that construction activity is temporarily ceased is less than 21 days) then stabilization measures do not have to be initiated on that portion of the site by the 14h day after construction activity	(i.e., until a Notice of Termination has been submitted) the are a crop of annual vegetation and a seeding of target perennial
temporarily ceased.	evidence of, or the potential for, pollutants entering the draina control measures identified in the Plan shall be observed to
<u>Structural Practices.</u> Structural practices will be implemented to divert flows from exposed soils or otherwise limit runoff and the discharge of pollutants from exposed areas of the site to the degree attainable. The practices identified on Sheet(s) C520, include but may not be limited to silt fences	ensure that they are operating correctly. Where discharge loc whether erosion control measures are effective in preventing
attainable. The practices, identified on Sheet(s) C520, include but may not be limited to silt fences, earth dikes, drainage swales, sediment traps, check dams, subsurface drains, pipe slope drains, level spreaders, storm drain inlet protection, rock outlet protection, reinforced soil retaining systems	(5). Based on the results of each inspection, the site descripti
level spreaders, storm drain inlet protection, rock outlet protection, reinforced soil retaining systems, gabions, temporary or permanent sediment basins and other measures design and implemented in	the Erosion, Sedimentation and Pollution Control Plan, the Pl days following each inspection. Implementation of such change
accordance with the Manual for Erosion and Sediment Control in Georgia, latest edition. The installation of these devices may be subject to Section 404 of the CWA.	seven (7) calendar days following each inspection.
orm Water Management	(6). A report of each inspection that includes the name(s) of c inspection, construction phase (i.e., initial, intermediate or fina
ctural measures should be placed on upland soils to the degree attainable. The	Erosion, Sedimentation and Pollution Control Plan, and action made and retained at the site or be readily available at a desi
Ilation of these devices may be subject to Section 404 of the CWA. This permit only addresses the Ilation of storm water management measures, and not the ultimate operation and maintenance of	construction site that has been phased has undergone final s reports shall be readily available by end of the second busine
n structures after the construction activities have been completed and the site has undergone final pilization. Operators are only responsible for the installation and maintenance of storm water	management practices that have not been properly installed a not identify any incidents, the inspection report shall contain a
anagement measures prior to final stabilization of the site, and are not responsible for maintenance	compliance with the Erosion, Sedimentation and Pollution Co V.G.2. of this permit.

after storm water discharges associated with construction activity have been eliminated from the site.

luding building materials, will not be discharged to waters of the state,

ds, and sediments and the generation of dust will be minimized or

the state and local waste disposal, sanitary sewer, and septic tank

for prevention of petroleum spills: All onsite vehicles will be monitored reventive maintenance to reduce the chance of leakage. Petroleum y sealed containers that are clearly labeled. Any petroleum to be rounded by an earthen berm as a secondary protective measure. Any will be applied according to the manufacture's recommendations. All pred and used in area that provides a secondary containment feature, with the least foreseeable impact if a catastrophic event should occur. nd procedures for spills shall be available on-site. for remediation of petroleum spills:

cturer's recommended methods for spill cleanup will be clearly posted nade available to site personnel.

necessary for spill cleanup will be kept in the material storage areas. uipment includes, but is not limited to, brooms, dustpans, mops, rags, r, sand, sawdust and properly labeled plastic and metal waste

and procedures will be reviewed after a spill and adjusted as

up immediately upon discovery. Ail spills will be reported as required by regulations.

CT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER), THE ENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1 _ 800 -- 426 - 2675

NOWN AMOUNT, THE NATIONAL RESPONSE CENTER (NRC) WILL BE HOURS AT 1 - 800 - 424 - 8802 or 1 - 202 - 426 - 2675. HAN 25 GALLONS AND NO SURFACE WATER IMPACTS OCCUR, THE E CONTACTED WITHIN 24 HOURS

25 GALLONS AND NO SURFACE WATER IMPACTS OCCUR, THE SPILL ND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED. the licensed professional who prepared this Plan if more than 1320 red onsite (this includes capacities of equipment) or if any one piece of

greater than 660 gallons. The contractor will need a Spill Prevention neasurers Plan prepared by that licensed professional. RS HAVE CHANGED. HIGHLIGHTED BOLD CONTACT NUMBERS ARE

ts - Containers for products such as fuels, lubricants, and tars will be

and spills. This includes onsite vehicles and machinery daily preventative maintenance of such equipment. Equipment maintenance ay from State Waters, natural drains, and storm water drainage inlets. Jeling tanks shall have a secondary containment liner to ntamination. Discharge of oils, fuels, and lubricants is prohibited.

will include collection in a suitable container and disposal as required

be done in accordance with one of the two following methods to charges on the site. oleum storage containers shall be covered with plastic sheeting or be

nder a temporary roof. oleum storage containers shall be located in a secondary containment

- All products will be stored in tightly sealed original containers when ct will not be discharged to the storm water collection system. Excess with these products, and product containers will be disposed of

er's specifications and recommendations. - NO concrete trucks will be allowed to wash out or discharge surplus

vater onsite ese products will be applied at rates that do not exceed the

ions or above the guidelines set forth in the crop establishment or in rosion and Sediment Control in Georgia. Any storage of these

oof in sealed containers. uilding or construction materials will be buried or disposed of onsite. disposed of in proper waste disposal procedures.

s will be stored in a staging area and covered with appropriate tarps pollution of storm water can occur. All materials to be stored on stone s, fuels, or similar to be kept in appropriate water tight containers to mmingling with storm water will occur.

vity has taken place at a primary

he primary permittee shall inspect: (a) all areas at the primary permittee's site andled for spills and leaks from vehicles and equipment and (b) all locations at or exit the site for evidence of off-site sediment tracking. These inspections

areas of the site that have not met final stabilization once every 24 hours except and non-working Federal holiday. The data collected for the purpose of e of the monitored activity. Measurement of rainfall may be suspended if all n or established a crop of annual vegetation and a seeding of target perennials

permittee) shall inspect the following at least once every seven (7) calendar hat is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any ring Sunday or any non-working Federal holiday in which case the inspection ss day and/or working day, whichever occurs first): (a) disturbed areas of the sed by the primary permittee for storage of materials that are exposed to Erosion and sediment control measures identified in the Plan applicable to the are that they are operating correctly. Where discharge locations or points are hether erosion control measures are effective in preventing significant impacts

tion or established a crop of annual vegetation and a seeding of target e must comply with Part IV.D.4.a.(4). These inspections must be conducted

permittee) shall inspect at least once per month during the term of this permit itted) the areas of the site that have undergone final stabilization or established et perennials appropriate for the region. These areas shall be inspected for ng the drainage system and the receiving water(s). Erosion and sediment

ischarge locations or points are accessible, they shall be inspected to ascertain preventing significant impacts to receiving water(s).

site description and the pollution prevention and control measures identified in Plan, the Plan shall be revised as appropriate not later than seven (7) calendar f such changes shall be made as soon as practical but in no case later than

name(s) of certified personnel making each inspection, the date(s) of each ediate or final), major observations relating to the implementation of the n, and actions taken in accordance with Part IV.D.4.a.(5). of the permit shall be ble at a designated alternate location until the entire site or that portion of a roone final stabilization and a Notice of Termination is submitted to EPD. Such cond business day and/or working day and shall identify all incidents of best ly installed and/or maintained as described in the Plan. Where the report does

all contain a certification that the best management practices are in Pollution Control Plan. The report shall be signed in accordance with Part

4. Maintenance

A. Inspections by a qualified personnel provided by the primary permittee and the associated records shall be kept on-site in compliance with GAR, 100001

B. Inspections of erosion control measures will be performed and corrective action taken when needed as required by the plan. C. The permittee shall maintain all erosion control measures until permanent vegetation has been established. D. The permittee shall clean out all sediment storage areas when required by the "MANUAL FOR EROSION AND SEDIMENT

CONTROL IN GEORGIA". E. Accumulated silt shall be removed when the silt is within 12" of the top of the silt fence utilized for erosion control.

5. Sampling Requirements.

A. Sampling Requirements

Sampling will occur at the outfall from the new detention pond. The unnamed tributary downstream of the proposed development is classified as state waters (supporting warm water fisheries). (See the Erosion and Sediment Control Plan, Sheet C520 for Sampling Location).

B. <u>Sample Type.</u>

All sampling shall be collected by "grab samples" and the analysis of these samples must be conducted in accordance with methodology and test procedures established by 40 CFR Part 136 (unless other test procedures have been approved); the guidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833-B-92-001" and guidance documents that may be prepared by the EPD.

(1). Sample containers should be labeled prior to collecting the samples.

(2). Samples should be well mixed before transferring to a secondary container.

(3). Large mouth, well cleaned and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid contamination.

(4). Manual, automatic or rising stage sampling may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection. However, samples from automatic samplers must be collected no later than the next business day after their accumulation, unless flow through automated analysis is utilized. If automatic sampling is utilized and the automatic sampler is not activated during the qualifying event, the permittee must utilize manual sampling or rising stage sampling during the next qualifying event. Dilution of samples is not required. Samples may be analyzed directly with a properly calibrated turbidimeter. Samples are not required to be cooled.

(5). Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in this permit must be reported to EPD as specified in Part IV.E.

C. Sampling Points.

(1). For construction activities the primary permittee must sample all receiving water(s), or all outfall(s), or a combination of receiving water(s) and outfall(s). Samples taken for the purpose of compliance with this permit shall be representative of the monitored activity and representative of the water quality of the receiving water(s) and/or the stormwater outfalls using the following minimum guidelines:

(a). The upstream sample for each receiving water(s) must be taken immediately upstream of the confluence of the first stormwater discharge

from the permitted activity (i.e., the discharge farthest upstream at the site) but downstream of any other stormwater discharges not associated with the permitted activity. Where appropriate, several upstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the upstream turbidity value.

(b). The downstream sample for each receiving water(s) must be taken downstream of the confluence of the last stormwater discharge from the permitted activity (i.e., the discharge farthest downstream at the site) but upstream of any other stormwater discharge not associated with the permitted activity. Where appropriate, several downstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the downstream turbidity value.

(c). Ideally the samples should be taken from the horizontal and vertical center of the receiving water(s) or the stormwater outfall channel(s).

(d). Care should be taken to avoid stirring the bottom sediments in the receiving water(s) or in the outfall stormwater channel.

(e). The sampling container should be held so that the opening faces upstream.

(f). The samples should be kept free from floating debris.

(g). Permittees do not have to sample sheet flow that flows onto undisturbed natural areas or areas stabilized by the project. For purposes of this section, stabilized shall mean, for unpaved areas and areas not covered by permanent structures and areas located outside the waste disposal limits of a landfill cell that has been certified by EPD for waste disposal, 100% of the soil surface is uniformly covered in permanent vegetation with a density of 70% or greater, or landscaped according to the Plan (uniformly covered with landscaping materials in planned landscaped areas), or equivalent permanent stabilization measures as defined in the Manual (excluding a crop of annual vegetation and a seeding of target crop perennials appropriate for the region).

(h). All sampling pursuant to this permit must be done in such a way (including generally accepted sampling methods, locations, timing, and frequency) as to accurately reflect whether stormwater runoff from the construction site is in compliance with the standard set forth in Parts III.D.3. or III.D.4., whichever is applicable.

D. <u>Sampling Frequency.</u>

(1). The primary permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event, the permittee shall sample at the beginning of any stormwater discharge to a monitored receiving water and/or from a monitored outfall location within in forty-five (45) minutes or as soon as possible.

(2). However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the stormwater discharge.

(3). Sampling by the permittee shall occur for the following qualifying events:

(a). For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a

stormwater discharge that occurs during normal business hours as defined in this permit after all clearing and grubbing operations have been

completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the sampling location:

(b). In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or

exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours as defined in this permit either 90 days after the first

sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location

selected as the sampling location, whichever comes first;

(c). At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours* until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained:

(d). Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not performed. Providing this justification does not relieve the permittee of any subsequent sampling obligations under (a), (b) or (c) above; and

(e). Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that have met the sampling

required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be required to conduct additional sampling other than as required by (c) above.

*Note that the permittee may choose to meet the requirements of (a) and (b) above by collecting turbidity samples from any rain event that reaches or exceeds 0.5 inch and allows for sampling at any time of the day or week.

SURFACE WATER DRAINAGE AREA: < 4.99 SQUARE MILES SITE SIZE: 10.01 to 25 ACRES MAXIMUM ALLOWABLE NTU = 50

It is anticipated that non-stormwater discharges will occur as part of the flushing and disinfection processes required for the potable water and fire service installed with this construction. This will include the main waterline and several hydrants. In all areas, the discharge is to be directed to the adjacent pavement to prevent scour. In addition, the location where this water exits the pavement will be observed during the discharge. If any evidence of erosion begins, the operation will be immediately stopped, and either altered to prevent erosion or delayed until completion of the installation of control measures.

1. The applicable permittees are required to submit the sampling results to the EPD at the address shown in Part II.C. by the fifteenth day of the month following the reporting period. Reporting periods are months during which samples are taken in accordance with this permit. Sampling results shall be in a clearly legible format. Upon written notification, EPD may require the applicable permittee to submit the sampling results on a more frequent basis. Sampling and analysis of any stormwater discharge(s) or the receiving water(s) beyond the minimum frequency stated in this permit must be reported in a similar manner to the EPD. The sampling reports must be signed in accordance with Part V.G.2. Sampling reports must be submitted to EPD using the electronic submittal service provided by EPD. Sampling reports must be submitted to EPD until such time as a NOT is submitted in accordance with Part VI.

Certification statement that sampling was conducted as per the Plan. 3. All written correspondence required by this permit shall be submitted by return receipt certified mail (or similar service) to the appropriate District Office of the EPD according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI.

1. The primary permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate location from commencement of construction until such time as a NOT is submitted in accordance with Part VI:

2. Copies of all Notices of Intent, Notices of Termination, inspection reports, sampling reports (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation) or other reports requested by the EPD, Erosion, Sedimentation and Pollution Control Plans, records of all data used to complete the Notice of Intent to be covered by this permit and all other records required by this permit shall be retained by the permittee who either produced or used it for a period of at least three years from the date that the NOT is submitted in accordance with Part VI. of this permit. These records must be maintained at the permittee's primary place of business or at a designated alternative location once the construction activity has ceased at the permitted site. This period may be extended by request of the EPD at any time upon written notification to the permittee.

All written correspondence required by this permit shall be submitted by **return receipt certified mail** (or similar service) to the appropriate District Office of the EPD. See address below:

E. <u>Turbidity Limitations</u>

1. In-stream discharge is not to increase turbidity in the receiving stream by more than twenty-five (25) nephelometric units (NTU) for waters supporting warm water fisheries, as stated in GAR 100001 Part III.C.3. 2. The outfall discharge from the NPDES Sample Location Point(s) is not to exceed the maximum allowable NTU value shown below as stated in GAR 100001 Part III.C.4 and from Appendix B.

Turbidity Requirements:

6. Non-Stormwater Discharges



2. All sampling reports shall include the following information:

The rainfall amount, date, exact place and time of sampling or measurements; b. The name(s) of the certified personnel who performed the sampling and

- measurements;
- c. The date(s) analyses were performed; The time(s) analyses were initiated;
- The name(s) of the certified personnel who performed the analyses;
- References and written procedures, when available, for the analytical techniques or methods used;
- g. The results of such analyses, including the bench sheets, instrument readouts, computer disks or tapes, etc., used to determine these results;
- h. Results which exceed 1000 NTU shall be reported as "exceeds 1000 NTU;" and

8. Retention of Records. (#32)

- A copy of all Notices of Intent submitted to EPD;
- A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit; The design professional's report of the results of the inspection conducted in accordance with Part IV.A.5. of this
- d. A copy of all sampling information, results, and reports required by this permit;
- A copy of all inspection reports generated in accordance with Part IV.D.4.a. of this permit;
- A copy of all violation summaries and violation summary reports generated in accordance with Part III.D.2. of this permit: and
- Daily rainfall information collected in accordance with Part IV.D.4.a.(2). of this permit

9. Report Submittal

EPD MOUNTAIN DISTRICT OFFICE (CARTERSVILLE)

P.O. BOX 3250 **16 CENTER ROAD CARTERSVILLE, GA 30121**

					5/6/24 RKA	Date Apr.
	s,				1. ISSUED FOR REVIEW	Rev. Description
	Date: Drawn by: Check by: 5/6/24 EAM RKA					
		COMPREHENSIVE	MONITORING PLAN			
	SITE DEVELOPMENT PLANS	FOR DO CONTRO A CTINIC	BZ CONTRACTING	WONLD READQUARTERS		LAND LOTS 73 AND 74 OF THE 5TH DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA
				NAL NA		
1						
	DI	RAW C	/ING 50		О.	

REID K ALMAND, P.E.


GSWCC LEVEL II #7975


GA PE #47263

(#1)


EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST	C508 Y 28 Description of the practices that will be used to reduce the pollutants in storm water discharges. *
STAND ALONE CONSTRUCTION PROJECTS	C500 Y 29 Description and chart or timeline of the intended sequence of major activities which disturb soils for the major
SWCD: <u>West Georgia</u> Project Name: <u>B2 Contracting World Headquarters</u> Address: 141 Hillwood Circle	portions of the site (i.e., initial perimeter and sediment storage BMPs, clearing and grubbing activities,
Local Issuing Authority: <u>City of Newnan</u> Date on Plans: <u>5/6/24</u>	excavation activities, utility activities, temporary and final stabilization).
Name & Email of person filling out checklist: Reid K. Almand, reid.almand@highlandllp.us	C501 Y 30 Provide complete requirements of Inspections and record keeping by the primary permittee. *
Plan Included TO BE SHOWN ON ES&PC PLAN	C501 Y 31 Provide complete requirements of Sampling Frequency and Reporting of sampling results. *
Page # Y/N C592 Y 1 The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission	C501 Y 32 Provide complete details for Retention of Records as per Part IV.F. of the permit *
as of January 1 of the year in which the land-disturbing activity was permitted.	C501 Y 33 Description of analytical methods to be used to collect and analyze the samples from each location. *
(The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed)	C501 Y 34 Appendix B rationale for NTU values at all outfall sampling points where applicable. *
C500 Y 2 Level II certification number issued by the Commission, signature and seal of the certified design professional.	C510 Y 35 Delineate all sampling locations, perennial and intermittent streams and other water bodies into which
(Signature, seal and Level II number must be on each sheet pertaining to ES&PC plan or the Plan will not be reviewed)	storm water is discharged. *
N/A 3 Limits of disturbance shall be no greater than 50 acres at any one time without prior written authorization from	C501 Y 36 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial sediment storage requirements and perimeter control BMPs, (2) intermediate grading and drainage
the GAEPD District Office. If GAEPD approves the request to disturb 50 acres or more at any one time, the Plan must	BMPs, and (3) final BMPs. For construction sites where there will be no mass grading and the initial perimeter
include at least 4 of the BMPs listed in Appendix 1 of this checklist and the GAEPD approval letter. *	control BMPs, intermediate grading and drainage BMPs, and final BMPs are the same, the Plan may combine
(A copy of the written approval by GAEPD must be attached to the plan for the Plan to be reviewed.)	all of the BMPs into a single phase. *
C500 Y 4 The name and phone number of the 24-hour contact responsible for erosion, sedimentation and pollution controls.	C510 Y 37 Graphic scale and North arrow.
C500 Y 5 Provide the name, address, email address, and phone number of primary permittee.	C510 Y 38 Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following: Map Scale Ground Slope Contour Intervals, ft
C500 Y 6 Note total and disturbed acreages of the project or phase under construction.	1 inch = 100ft or Flat 0 - 2% 0.5 or 1
C510 Y 7 Provide the GPS location of the construction exit for the site. Give the Latitude and Longitude in decimal degrees.	larger scale Rolling 2 - 8% 1 or 2
C500 Y 8 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.	Steep 8% + 2,5 or 10
C501 Y 9 Description of the nature of construction activity and existing site conditions.	N/A 39 Use of alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs as certified by a Design Professional (unless disapproved by GAEPD or the Georgia Soil
C500 Y 10 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary. C501 Y 11 Identify the project receiving waters and describe all sensitive adjacent areas including streams, lakes,	and Water Conservation Commission). Please refer to the Alternative BMP Guidance Document found at
residential areas, wetlands, marshlands, etc. which may be affected.	www.gaswcc.georgia.gov.
C500 Y 12 Design professional's certification statement and signature that the site was visited prior to development of the	N/A 40 Use of alternative BMP for application to the Equivalent BMP List. Please refer to Appendix A-2 of the Manual
ES&PC Plan as stated on Part IV page 19 of the permit	for Erosion & Sediment Control in Georgia 2016 Edition. *
C500 Y 13 Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate	N/A 41 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to state waters and any additional buffers required by the Local Issuing Authority. Clearly note and delineate all areas of impact.
and comprehensive system of BMPs and sampling to meet permit requirements as stated on Part IV page 19 of the permit *	C501 Y 42 Delineation of on-site wetlands and all state waters located on and within 200 feet of the project site.
C500 Y 14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days after installation."	C510 Y 43 Delineation and acreage of contributing drainage basins on the project site.
in accordance with Part IV.A.5 page 25 of the permit. *	C503 Y 44 Provide hydrology study and maps of drainage basins for both the pre- and post-developed conditions. *
C500 Y 15 Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot	C501 Y 45 An estimate of the runoff coefficient or peak discharge flow of the site prior to and after construction activities are
undisturbed stream buffers as measured from the point of wrested vegetation or within 25-feet of the coastal	completed.
marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variances and permits."	C602 Y 46 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without
N/A 16 Provide a description of any buffer encroachments and indicate whether a buffer variance is required.	erosion. Identify/Delineate all storm water discharge points.
C500 Y 17 Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on	C510 Y 47 Soil series for the project site and their delineation.
BMPs with a hydraulic component must be certified by the design professional." *	C510 Y 48 The limits of disturbance for each phase of construction.
C500 Y 18 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as	C501 Y 49 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment
authorized by a Section 404 permit." *	storage volume must be in place prior to and during all land disturbance activities until final stabilization of the
C500 Y 19 Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of	site has been achieved. A written justification explaining the decision to use equivalent controls when a
erosion and sediment control measures and practices prior to land disturbing activities."	sediment basin is not attainable must be included in the Plan for each common drainage location in which a
C500 Y 20 Clearly note statement that "Erosion control measures will be maintained at all times. If full implementation of the approved Plan does not provide for effective erosion control, additional erosion and sediment control measures	sediment basin is not provided. A written justification as to why 67 cubic yards of storage is not attainable must also be given. Worksheets from the Manual included for structural BMPs and all calculations used by the
shall be implemented to control or treat the sediment source."	storage design professional to obtain the required sediment when using equivalent controls. When discharging
C500 Y 21 Clearly note the statement "Any disturbed area left exposed for a period greater than 14 days shall be	from sediment basins and impoundments, permittees are required to utilize outlet structures that withdraw water
stabilized with mulch or temporary seeding."	from the surface, unless infeasible. If outlet structures that withdraw water from the surface are not feasible, a written justification explaining this decision must be included in the Plan.
N/A 22 Any construction activity which discharges storm water into an Impaired Stream Segment, or within 1 linear mile	C510 Y 50 Location of Best Management Practices that are consistent with and no less stringent than the Manual for
upstream of and within the same watershed as, any portion of a Biota Impaired Stream Segment must comply with Part III. C. of the permit. Include the completed Appendix 1 listing all the BMPs that will be used for those	Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with
areas of the site which discharge to the Impaired Stream Segment. *	legend.
N/A 23 If a TMDL Implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in	C601 Y 51 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.
Item 22 above) at least six months prior to submittal of NOI, the ES&PC Plan must address any site-specific	C600 Y 52 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting
conditions or requirements included in the TMDL Implementation Plan. *	dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time
C501 Y 24 BMPs for concrete washdown of tools, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum at the construction site is prohibited. *	of the year that seeding will take place and for the appropriate geographic region of Georgia.
C501 Y 25 Provide BMPs for the remediation of all petroleum spills and leaks.	* If using this checklist for a project that is less than 1 acre and not part of a common development
C501 Y 26 Description of the measures that will be installed during the construction process to control pollutants in storm	but within 200 ft of a perennial stream, the * checklist items would be N/A. Effective January
water that will occur after construction operations have been completed. *	Effective January
C501 Y 27 Description of practices to provide cover for building materials and building products on site. *	


			RKA Apr.
			5/6/24 Date
		┠┼┼┼┼┼	<u> </u>
			VIEW
			OR REV tion
			ISSUED FOR REVIEW Description
		┠┼┼┼┼┼	
ges. *			1. Rev.
soils for the major		Check by: RKA	
g activities,			
e. *		Drawn by: EAM	
*		Draw EAM	
· · · · ·		4	
location. *		Date: 5/6/24	
into which			
		ST	
ction site including: ding and drainage		T	
d the initial perimeter e Plan may combine		CK	
		CHECKLIST	
with the following:			
with the following:		н Ц	
		N.P.D.E.S.	
		N.I	
superior to) or the Georgia Soil			
cument found at			
A-2 of the Manual			IA
			EORG
and any additional pact			ίΤΥ, G
oject site.			COUN
od conditions *		Ţ,	WOKLD HEADQUAKTEKS LAND LOTS 73 AND 74 OF THE 5TH DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA
ed conditions. * truction activities are		ANS NG	L LK
		PLANS TING	
sharges without		NT P CTJ	D A
		MEN MEN R	
		ELOPM FOR NTR	EA lict, (
rary sediment basin, e location. Sediment		DEVEL	D H E.
I stabilization of the		SITE DEVELOPMENT PL FOR B2 CONTRACTIN	STH D
ntrols when a ication in which a			W UKLJ 4 of the 5th
s not attainable must ons used by the			74 OF
s. When discharging			AND
that withdraw water are not feasible,			ITS 73
he Manual for			ND LC
Chapter 6, with			Γ
eet the guidelines set			
			~
e species, planting for appropriate time			
jia.		No. 4126	
nent			DNAL
ffective January 1, 2024		D K. A	L MAIN
			_
	REID K ALMAND, P.E.		
	GA PE #47263		
	GSWCC LEVEL II #79754		
	GEUKGIA <mark>81</mark> .		
	www.Georgia811.com	C50)2





	: Drawn by: Check by: 24 EAM RKA 124 EAM 124 124 EAM 124 124 124 124 124 124 124 124 124 124	I. ISSUED FOR REVIEW 5/6/24 RKA Rev. Description Date Apr.
	DRAINAGE BASINS	
	SITE DEVELOPMENT PLANS FOR B2 CONTRACTING	WORLD HEADQUARTERS Land Lots 73 and 74 of the 5th district, city of Newnan, coweta county, georgia
REID K ALMAND, P.E. GA PE #47263 GSWCC LEVEL II #79754	DRAWING	






VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Du	DUST CONTROL ON DISTURBED AREAS		Du	Controlling surface and air movement of dust on construction site, roadways and similar sites.
Ds1	DISTURBED AREA STABILIZATION (WITH MULCHING ONLY)		Ds1	Establishing temporary protection for disturbed areas where seedlings may not have a suitable growing season to produce an erosion retarding cover.
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP SEEDING)		Ds2	Establishing a temporary vegetative cover with fast growing seedings on disturbed areas.

INTITIAL PHASE EROSION AND SEDIMENT CONTROL:

- THE PERIMETER SILT FENCE AND INLET SEDIMENT TRAPS SD2-A AND SD2-B, SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITIES.
- ALL AREAS OF DISTURBANCE WILL RECEIVE TEMPORARY GRASSING IF LEFT IDLE.
 DUST CONTROL WILL BE UTILIZED AS NECESSARY.
 SILT FENCE AND SEDIMENT TRAPS WILL BE CLEANED OUT OR EXCAVATED ONCE ONE-THIRD OF THE STORAGE DEPTH IS OBTAINED.

	HSG	CN	Area (acre)	AxCN			
Nooded	В	55	8.63	474.65			
		55.00	8.63				
EGEND							
XXX	EXISTING (CONTOUR	S				
xxx	PROPOSE	D INDEX C	ONTOURS				
XXX	PROPOSE	D INTERV	AL CONTOU	RS			
——×——×——	PROPOSE	O SILT FEI	NCE				
	TREE PROTECTION FENCE						
	LIMITS OF DISTURBANCE						
XX							





INITIAL PHASE EROSION AND SEDIMENTATION CONTROL PLAN

#37

IG TERS B2 CONTRACTINC WORLD HEADQUART

S

AENT PL.


VEL

DE

SITE

	ORE	5
C ₂	U DERK	
	er Co	ŃΙ
	No.4.265 PROFESSIONAL) *]
	6 e	/ /
X	OK. ALMA	
C	K. ALM	


DRAWING NO. C510




				_	CTICES							N. 1
CODE	PRACTICE	DETAIL	MAP SYMBO		DESCRIP ier to prevent sed		ving					5/6/24
Sd1	SEDIMENT BARRIER		(NDICATE TY	the cor bales c gravel,	nstruction site. It of straw or hay, b or a silt fence.	may be sandba brush, logs and p	igs, poles,					
Sd2	INLET SEDIMENT TRAP			around excavat comple	oounding area crea a storm drain dr ted area will be fi tion of constructi	op inlet. The illed and stabiliza on activities.	ed on					
Cd	CHECKDAM		ſ	across concent	l temporary barrie a swale, drainage trated flow.	ditch or area o	ructed of					R REVIEW
Co	CONSTRUCTION EXIT			constru removin public s	ned stone pad loc action site exit to ag mud from tires streets.	provide a place	e for ting					ISSUED FOR REVIEW
Sd4	TEMPORARY SEDIMENT TRAP			A small disturbe out. Th tempore	I temporary pond ed area so that s le principle feature ary sediment trap nt basin is the la	sediment can se e distinguishing • from a tempor	a rary		Check by: RKA		30'	
	VI	EGETAT	IVE F	PRA	CTICES						•_	-
CODE	PRACTICE	DETAIL	MAP SYMBO	L	DESCRIF	PTION			Drawn by: EAM		Ô	ļ
Du	DUST CONTROL ON DISTURBED AREAS		Du		ling surface and on construction site sites.				Date: 5/6/24		30' 15'	
Ds2	DISTURBED AREA STABILIZATION (WITH TEMP SEEDING)		Ds2		shing a temporary st growing seeding							
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)	11111111111111111111111111111111111111	Ds3	such as	shing a permanent s trees, shrubs, v s on disturbed ar	rines, grasses, or			PHASE	QN	NOL	
Su	SURFACE ROUGHENING		HSU-	depress	h soil surface wit sions on a conto ned condition afte	our or slopes lef	ft in a		NTERMEDIATE	EROSION A	SEDIMENTAT	
• <u>I</u> N Di • EX	NTERMEDIATE ISTURBANCE. XCAVATED SEI	SE EROSION AN PHASE WILL BE DIMENT TRAPS	GIN ON	CE THE	PROJECT MO			D	IT PLANS	CTING	UARTERS	E NEWNIAN COMETA COLINTY GEODGIA
 <u>I</u>N Di EX S C A Di S 	NTERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS LL AREAS OF UST CONTROL ILT FENCE AN	PHASE WILL BE	EGIN ON (Sd2'S) EIN. CUR ON WILL RI IZED AS RAPS W	CE THE WILL E ILY IN ECEIVE NECES ILL BE	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT	ED AROUND ECIFIED. RASSING IF I	THE LEFT ID	LE.	NT PL	B2 CONTRACTING	<i>NORLD HEADQUARTERS</i>	OF THE 5TH DISTRICT CITY OF NEWWAN CONVETA COUNTY GEORGIA
 <u>I</u>N Di EX S C A Di S 	NTERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS LL AREAS OF UST CONTROL ILT FENCE AN NE-THIRD OF	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT TI THE STORAGE	EGIN ON (Sd2'S) EIN. CUR ON WILL RI IZED AS RAPS W DEPTH	CE THE WILL E ILY IN ECEIVE NECES ILL BE	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT	ED AROUND ECIFIED. RASSING IF I	THE LEFT ID	LE.	- N	•)	Ŋ	3 AND 74 OF THE 5TH DISTRICT CHTY OF NEWNAN COMMETA COUNTY CEODGIA
 <u>I</u>N Di EX S C A Di S 	VTERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS UL AREAS OF UST CONTROL ILT FENCE AN INE-THIRD OF	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT T THE STORAGE	A	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED.	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT	THE LEFT ID	LE.	- N	•)	Ŋ	LOTS 73 AND 74 OF THE 5TH DISTRICT CITY OF NEWNIAN COMETA COLINITY CEODGIA
 <u>I</u>N Di EX S C A Di S 	NTERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS LL AREAS OF UST CONTROL ILT FENCE AN NE-THIRD OF	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT T THE STORAGE	GIN ON (Sd2'S) EIN. CUR ON WILL RI IZED AS RAPS W DEPTH	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED.	ED AROUND	THE LEFT ID	LE.	- N	•)	Ŋ	I AND LOTS 73 AND 74 OF THE 5TH DISTRICT CITY OF NEWAVAN COMETA COLINITY GEODGIA
 <u>I</u>N Di EX S C A Di S 	NTERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS LL AREAS OF UST CONTROL ILT FENCE AN INE-THIRD OF PRE De Land C Woode	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT T THE STORAGE	A	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED.	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ITERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS ILL AREAS OF UST CONTROL ILT FENCE AN INE-THIRD OF PRE De Land Co Woode POST E Land Co	PHASE WILL BE DIMENT TRAPS AS SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT TO THE STORAGE Weloped Basin over d	A B A B A A A A A A A A A A A A A	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT IS OBT 55 55.00	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED. Area (acre) 8.63 8.63 8.63	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT OR EXCAVAT AxCN 474.65	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ITERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS UST CONTROL ILT FENCE AN INE—THIRD OF PRE De Land Co Wooded POST E Land Co Impervi Open S	PHASE WILL BE DIMENT TRAPS AS SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT T THE STORAGE eveloped Basin over d Developed Basin over ious Areas	A B B B B B B C CUR ON WILL RI IZED AS RAPS W DEPTH	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT IS 55 55.00 CN 98 61	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED. Area (acre) 8.63 8.63 8.63 0 8.63 0 8.63	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ITERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS UST CONTROL ILT FENCE AN INE—THIRD OF PRE De Land Co Woode POST E Land Co Impervi	PHASE WILL BE DIMENT TRAPS AS SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT T THE STORAGE eveloped Basin over d Developed Basin over ious Areas	A B A B A A A A A A A A A A A A A	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT IS OBT 55 55.00 CN 98	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED. Area (acre) 8.63 8.63 8.63 0 8.63	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT OR EXCAVAT AxCN 474.65 AxCN 74.48	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ISTURBANCE. ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS UST CONTROL ILT FENCE AN NE—THIRD OF PRE De Land Co Wooder POST E Land Co Impervi Open S Gravel	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL D SEDIMENT T THE STORAGE	A B B B B CUR ON VILL RI IZED AS RAPS W DEPTH	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT S OBT	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED. Area (acre) 8.63 0 8.63 0 8.63 0 8.63 0 0.76 2.33 1.38	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT OR EXCAVAT AxCN 474.65 AxCN 74.48 142.13	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ISTURBANCE. ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS UST CONTROL ILT FENCE AN NE—THIRD OF PRE De Land Co Wooder POST E Land Co Impervi Open S Gravel	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL ND SEDIMENT TO THE STORAGE eveloped Basin over d Developed Basi over ous Areas pace	A B B B B n A1 HSG B B n A1 HSG B B	CE THE WILL E ILY IN ECEIVE NECES ILL BE IS OBT S OBT	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED. Area (acre) 8.63 0 8.63 0 8.63 0 8.63 0 0.76 2.33 1.38	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT OR EXCAVAT AxCN 474.65 AxCN 74.48 142.13	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ITERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS ULL AREAS OF UST CONTROL ILT FENCE AN INE-THIRD OF PRE De Land Co Wooded POST E Land Co Impervi Open S Gravel	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL D SEDIMENT TO THE STORAGE weloped Basin over d Developed Basin over ious Areas pace	A B B B B n A1 HSG B B n A1 HSG B B	CE THE WILL E ILY IN ECEIVE NECESS ILL BE IS OBT 6 55 55.00 CN 98 61 85 74.70	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SSARY. CLEANED OUT TAINED. Area (acre) 8.63 0 8.63 0 8.63 0 8.63 0 8.63 0 8.63 1.38 4.47	ED AROUND ECIFIED. RASSING IF I OR EXCAVAT OR EXCAVAT AxCN 474.65 AxCN 74.48 142.13 117.30	THE LEFT ID	LE.	- N	•)	Ŋ	
 <u>I</u>N Di EX S C A Di S 	ITERMEDIATE ISTURBANCE. XCAVATED SEI TRUCTURES A ONCRETE WAS UST CONTROL ILT FENCE AN INE-THIRD OF PRE De Land Co Woode POST E Land Co Gravel	PHASE WILL BE DIMENT TRAPS S SHOWN HER SHOUT WILL OC DISTURBANCE WILL BE UTIL D SEDIMENT TO THE STORAGE weloped Basin over d Developed Basin over ious Areas pace	A B B B A A A A A A A A A A A A A	CE THE WILL E ILY IN CEIVE NECES ILL BE IS OBT 55 55.00 CN 98 61 85 74.70	PROJECT MO BE IMPLEMENTI THE AREA SPE TEMPORARY G SARY. CLEANED OUT TAINED. Area (acre) 8.63 8.63 8.63 0 8.63 0 8.63 0 8.63 1.38 4.47 4.16	ED AROUND CIFIED. RASSING IF I OR EXCAVAT OR EXCAVAT AxCN 474.65 AxCN 74.48 142.13 117.30 AxCN AxCN	THE LEFT ID	LE.	- N	•)	Ŋ	

GEORGIA811.com

drawing no.





VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Ds3	DISTURBED AREA STABILIZATION (WITH PERM SEEDING)	1. V. V. C.	Ds3	Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ds4	DISTURBED AREA STABILIZATION (SODDING)	8	Ds4	A permanent vegetative cover using sods on highly erodable or critically eroded lands.
Ss	SLOPE STABILIZATION		Ss	A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.

FINAL PHASE EROSION AND SEDIMENT CONTROL:

- THE FINAL PHASE OCCURS ONCE THE SITE IS PAVED AND FULLY STABILIZED WITH PERMANENT GRASSING.
- ONCE SITE IS FULLY STABILIZED, ALL SEDIMENT TRAPS WILL BE REMOVED. PARKING AREAS TO BE SWEPT AND ALL CONSTRUCTION DEBRIS TO BE
- COLLECTED AND DISPOSED OF.
- STORM SYSTEM TO BE FLUSHED/OR VACUUMED PRIOR TO TURN-OVER.
- LIMITS OF Ds4 (SOD) TO BE PROVIDED ON THE LANDSCAPE PLAN.

<u>LEGEND</u>

	XXX —	
:	xxx-	
:	xxx-	
X	—x—	—x—

EXISTING CONTOURS PROPOSED INDEX CONTOURS PROPOSED INTERVAL CONTOURS PROPOSED SILT FENCE TREE PROTECTION FENCE LIMITS OF DISTURBANCE SOILS LIMITS



REID K ALMAND, P.E.

GA PE #47263

(#2)

DRAWING NO. C530

Ds1 MULCHING SPECIFICATIONS:

MULCH OR	TEMPORAR	Y GRASSING	SHALL BE APPLI	ED TO ALL EX	XPOSED AREAS	WITHIN 14 DAYS (OF DISTURBANCE	E. MULCH CAN
BE USED /	AS A SINGL	ILAR EROSION	CONTROL DEVIC	E FOR UP TO	O SIX MONTHS,	BUT IT SHALL	BE APPLIED A	T THE
APPROPRIA	TE DEPTH	, DEPENDING	ON THE MATERIA	AL USED, ANG	CHORED, AND H	AVE CONTINUOUS	90% COVER 0	R GREATER OF
THE SOIL	SURFACE.	MAINTENANCE	E SHALL BE REQ	JIRED TO MAI	INTAIN APPROPR	IATE DEPTH AND	90% COVER. T	EMPORARY
VEGETATION	N MAY BE	EMPLOYED IN:	STEAD OF MULCH	I IF THE ARE	A WILL REMAIN	UNDISTURBED FOR	R LESS THAN SI	IX MONTHS. IF
AN AREA \	WILL REMAIN	UNDISTURBE	ED FOR GREATER	THAN SIX M	IONTHS, PERMAN	IENT VEGETATION	FECHNIQUES SH	ALL BE
EMPLOYED.								

SITE PREPARATION I. GRADE TO PERMIT THE USE OF EQUIPMENT FOR APPLYING AND ANCHORING MULCH. 2. INSTALL NEEDED EROSION CONTROL MEASURES AS REQUIRED SUCH AS DIKES, DIVERSIONS, BERMS, TERRACES, AND SEDIMENT BARRIERS.

3. LOOSEN COMPACT SOIL TO A MINIMUM DEPTH OF 3 INCHES.

4. APPLY POLYETHYLENE FILM ON EXPOSED AREAS.

APPLYING MULCH WHEN MULCH IS USED WITHOUT SEEDING, MULCH SHALL BE APPLIED TO PROVIDE FULL COVERAGE OF THE EXPOSED AREA. 1. DRY STRAW OR HAY MULCH AND WOOD CHIPS SHALL BE APPLIED UNIFORMLY BY HAND OR BY MECHANICAL EQUIPMENT. 2. IF THE AREA WILL EVENTUALLY BE COVERED WITH PERENNIAL VEGETATION, 20-30 POUNDS OF NITROGEN PER ACRE IN ADDITION TO THE NORMAL AMOUNT SHALL BE APPLIED TO OFFSET THE UPTAKE OF NITROGEN CAUSED BY THE DECOMPOSITION OF THE ORGANIC MULCHES. 3. CUTBACK ASPHALT SHALL BE APPLIED UNIFORMLY . CARE SHOULD BE TAKEN IN AREAS OF PEDESTRIAN TRAFFIC DUE TO PROBLEMS OF "TRACKING IN" OF DAMAGE TO SHOES, CLOTHING, ETC.

ANCHORING MULCH

1. STRAW OR HAY MULCH CAN BE PRESSED INTO THE SOIL WITH A DISK HARROW WITH THE DISK SET STRAIGHT OR WITH A SPECIAL "PACKER DISK". DISKS MAY BE SMOOTH OR SERRATED AND SHOULD BE 20 INCHES OR MORE IN DIAMETER AND 8 TO 12 INCHES APART. THE EDGES OF THE DISK SHOULD BE DULL ENOUGH NOT TO CUT THE MULCH BUT TO PRESS IT INTO THE SOIL LEAVING MUCH OF IT IN AN ERECT POSITION. STRAW OR HAY MULCH SHALL BE ANCHORED IMMEDIATELY AFTER APPLICATION. STRAW OR HAY MULCH SPREAD WITH SPECIAL BLOWER-TYPE EQUIPMENT MAY BE ANCHORED WITH EMULSIFIED ASPHALT (GRADE AE-5 OR SS-1). THE ASPHALT EMULSION SHALL BE SPRAYED ONTO THE MULCH AS IT IS EJECTED FROM THE MACHINE. USE 100 GALLONS OF EMULSIFIED ASPHALT AND 100 GALLONS OR WATER PER TON OF MULCH. TACKIFIERS AND BINDERS CAN BE SUBSTITUTED FOR EMULSIFIED ASPHALT. PLEASE REFER TO SPECIFICATION Tb-TACKIFIERS AND BINDERS. PLASTIC MESH OR NETTING WITH MESH NO LARGER THAN ONE INCH BY ONE INCH SHALL BE INSTALLED ACCORDING TO

MANUFACTURER'S SPECIFICATIONS. 2. NETTING OF THE APPROPRIATE SIZE SHALL BE USED TO ANCHOR WOOD WASTE. OPENINGS OF THE NETTING SHALL NOT BE LARGER THAN THE AVERAGE SIZE OF THE WOOD WASTE CHIPS. 3. POLYETHYLENE FILM SHALL BE ANCHOR TRENCHED AT THE TOP AS WELL AS INCREMENTALLY AS NECESSARY

TEMPORARY SEEDING SPECIFICATIONS: Ds2

A. GRADING AND SHAPING

1. EXCESSIVE WATER RUNOFF MUST BE CONTROLLED BY PLANNED AND INSTALLED EROSION CONTROL PRACTICES SUCH AS CLOSED DRAINS, DITCHES, DIKES, DIVERSIONS, SEDIMENT BASINS, AND OTHERS.

B. SEEDBED PREPARATION

1. WHEN A HYDRAULIC SEEDER IS USED, SEEDBED PREPARATION IS NOT REQUIRED. 2. WHEN USING CONVENTIONAL OR HAND-SEEDING, SEEDBED PREPARATION IS NOT REQUIRED IF THE SOIL MATERIAL IS LOOSE AND NOT SEALED BY RAINFALL. 3. WHEN SOIL HAS BEEN SEALED BY RAINFALL OR CONSISTS OF SMOOTH UNDISTURBED CUT SLOPES, THE SOIL SHALL BE PITTED, TRENCHED, OR OTHERWISE

SCARIFIED TO PROVIDE A PLACE FOR SEED TO LODGE AND GERMINATE.

C. LIME AND FERTILIZER

1. AGRICULTURAL LIME IS NOT REQUIRED.

2. ON REASONABLY FERTILE SOILS OR SOIL MATERIAL, FERTILIZER IS NOT REQUIRED. 3. ON SOILS OF VERY LOW FERTILITY, USE 500 TO 700 POUNDS 10-10-10 FERTILIZER OR THE EQUIVALENT PER ACRE (12-16 lbs./1000 sq. ft.). IF THE SITE WILL PERMIT, APPLY BEFORE LAND PREPARATION AND DISK, RIP, OR CHISEL TO INCORPORATE.

D. SEEDING 1. SELECT A GRASS OR GRASS-LEGUME MIXTURE SUITABLE TO THE AREA AND SEASON OF THE YEAR. 2. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, DRILL, CULTIPACKER-SEEDER, OR HYDRAULIC SEEDER (SLURRY INCLUDING SEED AND FERTILIZER).

DRILL OR CULTIPACKER-SEEDERS SHOULD NORMALLY PLACE SEED ONE-HALF TO ONE INCH DEEP.

E. MULCHING TEMPORARY VEGETATION CAN, IN MOST CASES, BE ESTABLISHED WITHOUT THE USE OF MULCH. MULCH WITHOUT SEEDING SHOULD BE CONSIDERED FOR SHORT TERM PROTECTION. SEE Ds1 - DISTURBED AREA STABILIZATION (WITH MULCHING ONLY).

IRRIGATION IF WATER IS APPLIED, IT MUST BE AT A RATE NOT CAUSING RUNOFF AND EROSION. THOROUGHLY WET THE SOIL TO A DEPTH THAT WILL INSURE GERMINATION OF THE SEED. SUBSEQUENT APPLICATIONS SHOULD BE MADE WHEN NEEDED.

* REVISED 7/01 PER 5TH EDITION OF MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.

PERMANENT SEEDING SPECIFICATIONS:

Ds3

A. GRADING AND SHAPING 1. GRADING AND SHAPING IS NOT NORMALLY REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. VERTICAL BANKS SHALL BE SLOPED TO ENABLE PLANT ESTABLISHMENTS.

B. SEEDBED PREPARATION I. SEEDBED PREPARATION MAY NOT BE REQUIRED WHERE HYDRAULIC SEEDING AND FERTILIZING EQUIPMENT IS TO BE USED. 2. WHEN CONVENTIONAL SEEDING IS TO BE USED, SEEDBED PREPARATION WILL BE DONE AS FOLLOWS: A. BROADCAST PLANTING

1. TILLAGE AT A MINIMUM, SHALL ADEQUATELY LOOSEN THE SOIL TO A DEPTH OF 4 TO 6 INCHES; ALLEVIATE COMPATION; INCORPORATE LIME AND FERTILIZER; SMOOTH AND FIRM THE SOIL; ALLOW FOR THE PROPER PLACEMENT OF SEED SPRIGS, OR PLANTS; AND ALLOW FOR THE ANCHORING OF STRAW OR HAY MULCH IF A DISK IS TO BE USED.

C. LIME AND FERTILIZER - RATES AND ANALYSIS 1. WHERE PERMANENT VEGETATION IS TO BE ESTABLISHED, AGRICULTURAL LIME SHALL BE APPLIED AS INDICATED BY SOIL TEST OR AT THE RATE OF 1 TO 2 TONS PER ACRE. AGRICULTURAL LIME SHALL BE WITHIN THE SPECIFICATIONS OF THE GEORGIA DEPARTMENT OF AGRICULTURE. 2. LIME SPREAD BY CONVENTIONAL EQUIPMENT WILL BE "GROUND LIMESTONE". GROUND LIMESTONE IS CALCITIC OR DOLOMITIC

LIMESTONE GROUND SO THT 90 PERCENT OF THE MATERIAL WILL PASS THROUGH A 10-MESH SIEVE AND NOT LESS THAN 25 PERCENT WILL PASS THROUGH A 100-MESH SIEVE. 3. AGRICULTURAL LIME SPREAD BY HYDRAULIC SEEDING EQUIPMENT WILL BE "FINELY GROUND LIMESTONE." FINELY GROUND LIMESTONE IS CALCITIC OR DOLOMITIC LIMESTONE GROUND SO THAT 98 PERCENT OF THE MATERIAL WILL PASS THROUGH A 20-MESH SIEVE AND NOT LESS THAN 70 PERCENT WILL PASS THROUGH A 100-MESH SIEVE.

D. LIME AND FERTILIZER - APPLICATION 1. WHEN HYDRAULIC SEEDING EQUIPMENT IS USED:

A. THE INITIAL FERTILIZER WILL BE MIXED WITH SEED, INOCULANT (IF NEEDED) AND WOOD CELLULOSE OR WOOD PULP FIBER MULCH AND APPLIED IN A SLURRY. THE SLURRY WILL BE AGITATED DURING APPLICATION TO KEEP THE INGREDIENTS THOROUGHLY MIXED. THE MIXTURE WILL BE SPREAD UNIFORMLY OVER THE AREA WITHIN ONE HOUR

AFTER BEING PLACED IN THE HYDROSEEDER. B. FINELY GROUND LIMESTONE WILL BE MIXED WITH WATER AND APPLIED IMMEDIATELY AFTER MULCHING IS COMPLETED OR IN COMBINATION WITH THE TOP DRESSING.

2. WHEN CONVENTIONAL PLANTING IS TO BE DONE, LIME AND FERTILIZER WILL BE APPLIED UNIFORMLY IN ONE OF THE

FOLLOWING WAYS: A. APPLY BEFORE LAND PREPARATION SO THAT IT WILL BE MIXED WITH THE SOIL DURING SEEDBED PREPARATION; OR, B. MIX WITH THE SOIL USED TO FILL THE HOLES, DISTRIBUTE IN FURROWS; OR,

C. BROADCAST AFTER STEEP SURFACES AND SCARIFIED, PITTED OR TRENCHED. D. A FERTILZER PELLET WILL BE PLACED AT ROOT DEPTH.

* REVISED 7/01 PER 5TH EDITION OF MANUAL FOR EROSION & SEDIMENT CONTROL IN GEORGIA.

BERMUD (CYNODC HULLE

ALONE WITH OT BERMUD (CYNODC UNHU WITH TEI WITH OT

CENTIPEI (EREMOC OPHIL

FESCUE, (FESTUC ALONE WITH OT

LESPEDE (LESPED

SCARIFIE

UNSCARI

SEED-BE

LOVEGRA (ERAGRC


ALONE


WITH OTH


	Ds2	DISTURBED) AREA STA	BILIZ	ZATI	ON (WITH	TEN	1P0	RAF	RY SEEDINGS)
SPECIES		BROADCAST RATES 2/ – PLS 3/			PLANTING RATES BY RESOURCE AREA PLANTING DATES					REMARKS
	PER ACRE	PER 1000 SQ. FT.	AREA	JF		RMISSIBLE B	A S			
MILLET, PEARL (PENNESETUM GLAUCUM) ALONE	50 LBS	1.1 LB	M-L P C		-		-			88,000 SEED PER POUND. QUICK DENSE COVER. MAY REACH 5 FEET IN HEIGHT. NOT RECOMMENDED FOR MIXTURES.
RYEGRESS, ANNUAL (LOLIUM TEMULENTUM) ALONE	40 LBS	0.9 LB	M-L P C		-					227,000 SEED PER POUND. DENSE COVER. VERY COMPETITIVE VERY COMPETITIVE AND IS NOT TO BE USED IN MIXTURES
SUDANGRASS (SORGHUM SUDANESE) ALONE	60 LBS	1.4 LB	M-L P C		-		-			55,000 SEED PER POUND. GOOD ON DROUGHTY SITES. NOT RECOMMENDED FOR MIXTURES.
MILLET, BROWNTOP (PANICUM FASCICULATUM) ALONE IN MIXTURES	40 LBS 10 LBS	0.9 LB 0.2 LB	M-L P C				-			137,000 SEED PER POUND. QUICK DENSE COVER. WILL PROVIDE TOO MUCH COMPETITION IN MIXTURES IF SEEDED AT HIGH RATES.


Ds3 DISTURBED AREA STABILIZATION (WITH PERMANENT SEEDINGS)														
SPECIES	BROADCAST RATES 2/ – PLS 3/ PER PER ACRE 1000 SQ. FT.		RESOURCE AREA	PLANTING RATES BY RESOURCE AREA PLANTING DATES OPTIMUM PERMISSIBLE BUT MARGINAL J F M A M J J A S O N D							GINAL	_		
IDA, COMMON DON DACTYLON) LED SEED DTHER PERENNIALS	10 LBS 6 LBS	0.2 LB 0.1 LB	P C	-				_				1,787,000 SEED PER POUND. QUICK COVER. LOW GROWING AND SOD FORMING. FULL SUN. GOOD FOR ATHLETIC FIELDS.		
IDA, COMMON DON DACTYLON) IULLED SEED EMPORARY COVER DTHER PERENNIALS	10 LBS 6 LBS	0.2 LB 0.1 LB	P C									PLANT WITH WINTER ANNUALS. PLANT WITH TALL FESCUE.		
PEDE OCHLOA IIUROIDES)	BLOCK S	OD ONLY	P C			-						DROUGHT TOLERANT. FULL SUN OR PARTIAL SHADE. EFFECTIVE ADJACENTTO CONCRETE AND IN CONCENTRATED FLOW AREAS. IRRIGATION AS NEEDED UNTIL FULLY ESTABLISHED. DO NOT PLANT NEAR PASTURES. WINTERHARDY AS FAR NORTH AS ATHENS AND ATLANTA.		
E, TALL JCA ARUNDINACEA) DTHER PERENNIALS	50 LBS 30 LBS	1.1 LB 0.7 LB	M-L P									227,000 SEED PER POUND. USE ALONE ONLY ON BETTER SITES. NOT FOR DROUGHTY SOILS. MIX WITH PERENNIAL LESPEDEZAS OR CROWNVETCH. APPLY TOPDRESSING IN SPRING FOLLOWING FALL PLANTINGS. NOT FOR HEAVY USE AREAS OR ATHLETIC FIELDS.		
DEZA, SERICEA EDEZA CUNEATA) TED	60 LBS	1.4 LB	M-L P C	-			_					350,000 SEED PER POUND. WIDELY ADAPTED. LOW MAINTENANCE. MIX WITH WEEPING LOVEGRASS, COMMON BERMUDA, BAHIA, OR TALL FESCUE. TAKES 2 TO 3 YEARS TO BECOME FULLY ESTABLISHED. EXCELLENT ON ROAD BANKS. INOCULATE SEED WITH EL INOCULANT.		
RIFIED	75 LBS	1.7 LB	M-L P C									MIX WITH TALL FESCUE OR WINTER ANNUALS.		
BEARING HAY	3 TONS	138 LB	M-L P C									CUT WHEN SEED IS MATURE. BUT BEFORE IT SHATTERS. TALL FESCUE OR WINTER ANNUALS.		
RASS, WEEPING ROSTIS CURVULA) DTHER PERENNIALS	4 LBS 2 LBS	0.1 LB 0.05 LB	M-L P C									1,500,000 SEED PER POUND. QUICK COVER. DROUGHT TOLERANT. GROWS WELL WITH SERICEA LESPEDEZA ON ROADBANKS.		


#52 DISTURBED AREA STABILIZATION WITH MULCHING, TEMPORARY SEEDINGS AND PERMANENT SEEDINGS Ds2 Ds1 SCALE: NTS DATE:1/24/04














7" 4000 PSI FIBER MESH REINFORCED CONCRETE 8888888888 CONCRETE PAVING DETAIL SCALE: N.T.S. -EXP. JOINT 20' O.C.-Δ 1 A Δ. . Δ΄ -AS INDICATED-GRADE _____∆ · -3000 PSI CONCRETE ----<u>SECTION A</u> CONCRETE SIDEWALK DETAIL SCALE: N.T.S.

OG APPROVED FILL IN 6" COMPACTED LIFTS. GAB PAVEMENT SECTION SCALE: N.T.S.











						4 RKA	e Apr.				
						5/6/24	Date				
						1. ISSUED FOR REVIEW	Rev. Description				
Date: Drawn by: Check by: 5/6/24 EAM RKA							R				
CONSTRUCTION DETAILS											
SITE DEVELOPMENT PLANS	FOR		B2 CUNIKACIING	WORLD HEADOLLARTERS			LAND LOTS 73 AND 74 OF THE 5TH DISTRICT, CITY OF NEWNAN, COWETA COUNTY, GEORGIA				
				E R BION E E A L	NAL R						













S-001





GRADE-LINE




Inspected By:










เ 6/772006 " (1:00:07 " พมิ 5 \GDDT-DSW1 \GDPLDT\ QCF \ ฐอ_T (? f _อน) อน1. "gef" ฐอพอกร โมะ \ GARY \ 7019A " คำX \ 7019A. "อา?"

alis)100 Series - Pipe Installation/WDS\101_Standard_Trench_Installation.dwg, Model, 8/30/2007 4:14:23 PM, trader, CutePDF Wri





L			4"		21'							
		6"		23'								
	OVER TO PAVEMENT, H	8"		26'								
		10"		28'	,							
		12"		30'								
	<u> </u>		15"		34"							
LL			18"		39'							
			24"		48'							
NCH			30"		56'							
ING			36"		64'							
			42"		72"							
ABLE IDATIC	N		48"		80'							
			54"		88'							
		60"		96'	•							
MINIMUM RECOMMENDED COVER BASED ON VECHICLE LOADING CONDITIONS												
			SUR	FACE I	IVE LOADI	NG CC	NDITIC	DN N	7			
	PIPE DIA	И.	H-25				ISTRUC E LOAD		1			
	12" - 48'		12"				3"	- <u>-</u>	1			
	54" - 60'	54" - 60"				60)"		1			
	* VEHICLE	S IN E	XCESS C	F 75T	MAY REQU	IIRE AD	DITIO	VAL CO	_ √ER			
					ENDED CO							
				ADING CO COOP								
			AIVI.	E-80*	*	_						
		UP TO	24"	24"								
		30"-3		36"								
			42"-6	60"	48"							
** COVER IS MEASURED FROM TOP OF PIPE TO BOTTOM OF RAILWAY TIE.												
				REME	NTS, ARE C	ONLY A	PPLICA	\BLE				
	TO A	STM F	= 2306 PIF	°E.								
2	ADDED E-80 IN	ION	TJR	08/20/07								
REV.	DESCRI	PTION		BY	MM/DD/YY	CHK'D						
					•			DRAW	CKS			
TYPICAL TRENCH					AN BLVD 110 43026	CK10	10/18/06 m					
DETAIL			<u>11111/</u>		SCALL	NTS						
IG NUMBER: STD-101			ADVANCED DR/	AINAGE SYST	EMS, INC.			-	NTS 1 OF 1			

